

P1				Length = 1m, 2m, or 3m				P2			
MCIL8M								MCIL8F			
1	BATT_POS	20 AWG	BLACK	BLACK	20 AWG	BATT_POS	1	1	BATT_POS	20 AWG	BLACK
2	BATT_POS	20 AWG	WHITE	WHITE	20 AWG	BATT_POS	2	2	BATT_POS	20 AWG	WHITE
3	BATT_NEG	20 AWG	RED	RED	20 AWG	BATT_NEG	3	3	BATT_NEG	20 AWG	RED
4	BATT_NEG	20 AWG	GREEN	GREEN	20 AWG	BATT_NEG	4	4	BATT_NEG	20 AWG	GREEN
5	COMM_A	20 AWG	ORANGE	ORANGE	20 AWG	COMM_A	5	5	COMM_A	20 AWG	ORANGE
6	COMM_B	20 AWG	BLUE	BLUE	20 AWG	COMM_B	6	6	COMM_B	20 AWG	BLUE
7	TRIG_OUT	20 AWG	WHITE / BLACK	WHITE / BLACK	20 AWG	TRIG_OUT	7	7	TRIG_OUT	20 AWG	WHITE / BLACK
8	TRIG_IN	20 AWG	RED / BLACK	RED / BLACK	20 AWG	TRIG_IN	8	8	TRIG_IN	20 AWG	RED / BLACK

MONTEREY BAY AQUARIUM RESEARCH INSTITUTE

7700 SANDHOLDT ROAD

MOSS LANDING, CA 95039

(831) 775-1700 www.mbari.org

Copyright MBARI 2000



Title**SeeStar II Intermodule Cable Schematic**Number**11021185-6**

Size**B**Engineer**Chad Key**Layout**<Layout Eng.>**Filename**<Filename>**Rev**A**

Date**Wednesday, July 29, 2015**Sheet**1**of**1**

This work is distributed under a Creative Commons Attribution-ShareAlike 4.0 License