


*** MBARI will provide Falmat for cable Assembly



MINK-10-CCPL


One End Molded Only

- Pin 1 - Orange (+24V)
- Pin 2 - Yellow RX232
- Pin 3 - Red TX232
- Pin 4 - Blue TX+
- Pin 5 - Green TX-
- Pin 6 - Gray RX+
- Pin 7 - White RX-
- Pin 8 - COAX Center NTSC
- Pin 9 - Coax Shield \ Cable Shield
- Pin 10 - Blue (Return)

Twisted Pair
Twisted Pair

Title		
Time Lapes Camera		
Size A	Document Number 8675309	Rev A
Date:	Wednesday, September 28, 2011	Sheet 1 of 1

*** MBARI will provide Falmat for cable Assembly



MINK-10-CCPL

One End Molded Only

- Pin 1 - Orange (+24V)
- Pin 2 - Yellow RX232
- Pin 3 - Red TX232
- Pin 4 - Blue TX+
- Pin 5 - Green TX- Twisted Pair
- Pin 6 - Gray RX+
- Pin 7 - White RX- Twisted Pair
- Pin 8 - COAX Center NTSC
- Pin 9 - Coax Shield \ Cable Shield
- Pin 10 - Blue (Return)

Title		
Time Lapes Camera		
Size A	Document Number 8675309	Rev A
Date: Wednesday, September 28, 2011 Sheet 1 of 1		