




P12
MCIL6M


1	24V RET (LIGHT 3)	BLACK	20 AWG
2	24V (LIGHT 3)	WHITE	20 AWG
3	24V (LIGHT 4)	RED	20 AWG
4	24V RET (LIGHT 4)	GREEN	20 AWG
5	N/C	ORANGE	20 AWG
6	N/C	BLUE	20 AWG

Mates with MCBH6F
[Core J-Box C5]

Female Locking
Sleeve
MC-DLS-F



MCIL6FS
Female Face View




MCBH6MP
Male Face View

P2
MCIL5F


20 AWG	BLACK	+24 V	1
20 AWG	WHITE	24 V Return	2
20 AWG	RED	Frame	3
20 AWG	GREEN	N/C	4
20 AWG	ORANGE	Dimmer	5

Mates with MCBH5M
[SeaLite Sphere NIR]

Female Locking
Sleeve
MC-DLS-F



MCIL5F
Female Face View



MCBH5MP
Male Face View



Monterey Bay Aquarium Research Institute
7700 Sandhold Road, Moss Landing, CA 95039

Engineer <Engineer>	Size A	Document Number <Doc>	Title Mini-ROV: NIR light cable		Project <Project>
Designer <Designer>	Date: Tuesday, March 15, 2016		Part Number <Part Number>	Project File <Project File>	Rev <Rev>

Sheet 1 of 1