

P1  
MCIL4M




|   |              |             |       |
|---|--------------|-------------|-------|
| 1 | 24V RET      | 22AWG       | BLACK |
| 2 | 24V          | 22AWG       | RED   |
| 3 | VIDEO        | COAX        |       |
| 4 | VIDEO SHIELD | COAX SHIELD |       |

Falmat Xtreme Green  
Video Cable  
PN# FM070901-4

Length = 8'

|             |       |              |
|-------------|-------|--------------|
| 22AWG       | BLACK | 24V RET      |
| 22AWG       | RED   | 24V          |
| COAX        |       | VIDEO        |
| COAX SHIELD |       | VIDEO SHIELD |

P2  
MCIL4F



|   |
|---|
| 1 |
| 2 |
| 3 |
| 4 |



**Monterey Bay Aquarium Research Institute**

7700 Sandhold Road, Moss Landing, CA 95039

Title

MiniROV: Camera Cable

Engineer  
Chad Kocy

Size  
A

Document Number  
<Doc>

Layout  
<Layout>

Date: Monday, April 15, 2013

Layout File

<Layout File>

Rev  
<Rev>

Sheet 1 of 1