

Metal Series Key Features



- Slim Style
- Wide Power Range: 10W-300W
- Universal Input:
10W-30W: 85-264V AC/105-370V DC
50W-300W: 85-264V AC/105-350V DC
- Screw Terminals , IP20 (fingersafe)
- Power Fault protection
EN61000-3-2
EN61000-3-3 (50W to 300W models)
- Overcurrent/Overvoltage protection
- Voltage ± 10% adjustment
- DIN rail or Panel Surface Mount
- Approvals:
CE marked
UL 508 listed
UL 1950 recognized
EN50178 compliant
EMC Directives
EN50081-2
EN61000-6-2
LVD EN60950:2000



PS3L Metal Power Supplies



10 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-A05AFF	5V DC	2A
PS3L-A12AFF	12V DC	0.9A
PS3L-A24AFF	24V DC	0.5A



15 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-B05AFF	5V DC	3A
PS3L-B12AFF	12V DC	1.4A
PS3L-B24AFF	24V DC	0.7A



30 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-C05AFF	5V DC	6A
PS3L-C12AFF	12V DC	2.5A
PS3L-C24AFF	24V DC	1.3A



50 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-D12AFF	12V DC	4.3A
PS3L-D24AFF	24V DC	2.2A



100 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-E12AFF	12V DC	8.5A
PS3L-E24AFF	24V DC	4.5A



150 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-F12AFF	12V DC	13A
PS3L-F24AFF	24V DC	6.5A



300 Watt Power Supply

Part Number	Rated Voltage	Rated Current
PS3L-G24AFF	24V DC	12.5A

Metal Power Supply Dimensions

