


DEESEA
POWER & LIGHT



Nano SeaLite®

Compact. Durable. Astonishing Light Output for its Size.



FEATURES


6000 m Depth Rated

7-32V DC Input Power

Compact and Ultra Lightweight

700 Lumens Typical Light Output

Highly Vibration and Shock Resistant



T: (858) 576-1261
F: (858) 576-0219

4033 Ruffin Road
San Diego, CA
92123- 1817 USA

www.deepsea.com
sales@deepsea.com



Nano SeaLite®

Standard Connector






MCBH4MP

- 1 = Negative (-)
- 2 = Positive (+)
- 3 = Not Used
- 4 = Not Used

*Other Connectors Available

Dimensions



Mechanical Specifications	
Body Material	Hard Anodized 6013-T8 Aluminum
Window Material	Sapphire
Mounts	High Strength Plastic Mounting Collar (Standard) Helmet Mounting Brackets with Quick Release (Optional)
Weight in Air	113.7 g (4.01 oz)
Weight in Water	54.99 g (1.94 oz)
Implodible Volume	TBD
Length (w/o Connector)	4.99 cm (1.97 in)
Outer Diameter	2.50 cm (0.98 in)
Environmental Specifications	
Depth Rating	6000 m (20,000 ft)
Test Pressure	10,000 psi
Crush Depth	TBD
Min/Max Operation Temp.	-10° C to 50° C (14° F to 122° F)
Optical Specifications	
Color	White
Lumens in the Water	700 Lumens Typical
Color Temp	Standard: 7200° K (White LED)
Beam Pattern (FWHP)	TBD
Electrical Specifications	
Input Voltage Range	7-32Vdc
Input Current	2A @ 7V, 0.45A @ 32V
Input Power	14 W



DEEPSEA
POWER & LIGHT®

T: (858) 576-1261
F: (858) 576-0219

4033 Ruffin Road
San Diego, CA 92123- 1817 USA

www.deepsea.com
info@deepsea.com

