

[13 MegaPixel USB 3.0 CMOS Color Camera](#) NEW

[English](#) | [United States](#) 



- [Company](#)
- [Products](#)
- [Support](#)
- [Media Center](#)
- [Resellers](#)

[Products](#) [Industrial Cameras](#) [USB 3.0 Mono](#)

Products

- [Industrial Cameras](#)
 - [USB 3.0 Mono](#)
 - [USB 3.0 Color](#)
 - [USB 2.0 Mono](#)
 - [USB 2.0 Color](#)
 - [GigE Mono](#)
 - [GigE Color](#)
 - [FireWire 800 Mono](#)
 - [FireWire 800 Color](#)
 - [FireWire 400 Mono](#)
 - [FireWire 400 Color](#)
- [Cameras with Integrated Optics](#)
- [Board Cameras](#)
- [Autofocus Cameras](#)
- [Zoom Cameras](#)
- [Converters](#)
- [Grabbers](#)
- [Software](#)
- [Optics](#)
- [Accessories](#)

USB 3.0 Mono

USB 3.0 MONOCHROME INDUSTRIAL CAMERAS

The Imaging Source USB 3.0 monochrome industrial cameras have been designed for high performance and

challenging applications. They are equipped with highly sensitive CMOS or CCD sensors from Sony and Aptina, and feature a variety of input, output, strobe and trigger options via an external Hirose port. The USB 3.0 industrial cameras are manufactured with multiple resolutions and frame rates, so you can easily find the right one for your application. Their compact 29 x 29 mm case and highly competitive price make these cameras a popular choice for demanding applications.

- Device driver and drivers compatible to TWAIN, VisionPro AIK, ActivVisionTools, HALCON, LabVIEW and Matlab for Windows XP, Vista, 7 and 8.
- IC Capture camera control and acquisition software for Windows XP, Vista, 7 and 8.
- IC Imaging Control Software Development Kit (SDK) as .NET, ActiveX and C++ class library for Windows XP, Vista, 7 and 8.
- Resolution: VGA to 5 MP.
- Frame rate: Up to 120 fps.
- Dimensions: 29 x 29 x 43 mm.
(ideal for embedded systems).
- Wide range of monochrome CMOS and CCD sensors.
- Compatible to C and CS mount lenses.
- High performance and competitive price.
- High stability, flexibility and customer satisfaction.

	<u>Order Code</u>	<u>Res</u>	<u>FPS</u>	<u>Format</u>	<u>Sensor</u>	<u>Type</u>	<u>Shutter</u>	<u>Price</u>
	DMK 23UV024	752x480	100	1/3 "	Aptina MT9V024	CMOS	Global	\$398.00
	DMK 23UM021	1280x960	60	1/3 "	Aptina MT9M021	CMOS	Global	\$449.00
	DMK 23U618	640x480	120	1/4 "	Sony ICX618ALA	CCD	Global	\$450.00
	DMK 23UP031	2592x1944	15	1/2.5 "	Aptina MT9P031	CMOS	Rolling	\$499.00
	DMK 23U445	1280x960	30	1/3 "	Sony ICX445ALA	CCD	Global	\$650.00
	DMK 23U274	1600x1200	20	1/1.8 "	Sony ICX274AL	CCD	Global	\$850.00

Subject to change

© 1991-2014 The Imaging Source Europe GmbH [Contact Us](#) [AGBs](#) [Sitemap](#) [Imprint](#) [Camera Scanner](#)



[ISO 9001:2008 certified](#)