



Tiny: SV3 Pre-Launch Checklist

SV3 Pre-Launch Checklist

Date	2019-05-13T18:30:19.363Z	Glider Name	SV3-794595959(Tiny)
Tech(s)	cwahl	Organization	MBARI
Payload(s)	g2, s1, s2 and s3	Project	CANON
Ship/Op Area	Paragon MB	Location	Using GPSUblox declination=13.028529, fail

Software Information

Id	Tiny, sn=794595959, Running Regulus 1.1.1, software version of 2016-08-24T17:05:27Z, production
----	---

Communication

Item/Procedure	Readings	Initials
WiFi Connection	WiFi is On	☒
Virtual Relay	ON. 0 queued msgs (Max=2500). Channel is WAITING.(no internet connectivity)	☒
WGMS Iridium	ON. 0 queued msgs (Max=1). Channel is TALKING. IMEI:300434060708190, consecutiveErrors=0,	☒
Vehicle telemetry received		☒
Tracker telemetry received	Battery (bars) 15.7 v Report Rate 4 hrs	☒

Configuration

Item/Procedure	Readings	Specifications	Initials
Topside RDF Frequency	n/a		☒
Hull RDF Frequency	n/a		☒
Tracker WGMS name	Tiny Tracker		☒
Drybox WGMS name	SV3-011 Tiny		☒
Float name	Tiny		☒
Glider name	Tiny v1.5		☒
Thruster Serial Number	2c001c	Last 6 digits of Hardware ID found on AMPS page	☒
Event definitions		Compare against standard list	☒
Vehicle and tracker op area defined		Note area name(s) and enable alarms	☒
Escalation list created/populated			☒

Vehicle Status

Item/Procedure	Readings	Initials
Battery [Wh] > 700 Wh	854.854	☒
Solar Power Indicators: > 0	21.181 0.0 31.807 28.43	☒

Item/Procedure	Readings				
Domain Info	AMPS Hardware Status	Temperature (°C)	Pressure (kPa)	Hardware Uptime	Initials
Domain_Name=Host, Node=1, HW_SerNum=0x3132471639323739002d0037 On=Y	OK	23.1	115.1	Uptime: 0 days, 02:57:17	☒
Domain_Name=Thruster-2, Node=3, HW_SerNum=0x3333470738373634002c001c On=Y	OK	23.0	167.2	Uptime: 0 days, 02:52:52	☒
Domain_Name=PyldInt-0x3332470932363032002b0025, Node=5, HW_SerNum=0x3332470932363032002b0025 On=Y	OK	17.8	118.8	Uptime: 0 days, 00:03:51	☒

Mechanical Checks

	Item/Procedure	Specifications	Initials
Float	Wet-mates connected/lubed	3M Silicone Lubricant Spray: 3M ID No. 62-4678-4930-3	☒
	Connector covers secure		☒
	Drybox secure	Wiggle test	☒
	Contact info secure		☒
	Hull	Free of cracks and dings	☒
	Skeg/Fin	Secure	☒
Sub	Hardware secure		☒
	Umbilical visual inspection	Free of voids/defects	☒
	Roll pins inserted	Flushed with surface	☒
	Wings	Hardware secure with Loctite and Lock Nuts	☒
	Thruder	Hardware secure	☒

Vehicle Functionality

Item/Procedure	Readings	Specifications	Initials
Thruster Spin	435.0	Spins freely, slow and fast speeds	☒
Rudder Range of Motion		Rudder moves freely and smoothly	☒
Rudder right, left, center	Rudder(2019-05-13T18:30:14.436Z,desiredHeading=346.7,compass=36.7,rack=-12.9,post=-15rudd	Right, Left, Center	☒
Thruder Compass Correction	Thruder compass is NOT corrected		☒
Fixed heading test (spin)	180	Avoidance Off, Note Heading Used	☒
Waypoint course test (spin)	41	Avoidance Off, Note Waypoint Course Used	☒
Buoy Release Mechanism	device is disarmed, deviceState=OFF, deployCounter=0	Catch release buoy by hand	☒
Octopus Cable 01	OK	Must Pass	☒
Octopus Cable 02	OK	Must Pass	☒
AIS Status	MMSI 367375360 (OCEAN ANGEL 3). Pos=36.804363, -121.785170. t=30:0:UNDERWAY_SAILING	If in harbor, must see MMSI	☒
Photo Document			☒

Vehicle Communication and Telemetry

Item/Procedure	Readings / Specifications	Init
WX reporting	Temp=NaN°C, Press=NaNmb, Wind Speed=NaNkn, Wind Dir=NaN°. Heading=NaN°	☒
UBLOX GPS	2019-05-13T18:30:18Z@36.802324,-121.7871537, lastRx=0.529s, quality=100, clockDt=3.204s	☒
Airmar GPS	Not Available!	☒
Torpedo GPS	2019-05-13T18:30:20Z@36.8023286,-121.7871798, lastRx=1.499s, quality=65, clockDt=1.206s	☒
Water speed readings	Out of the water; Unknown speed; Not yet running, powerState=OFF, ampsPower=false	☒
Obstacle Avoidance Status	Enabled	☒
RDF beacon tested w/receiver		☐
Check alarms	"Out of bounds" red. All yellow/green	☒

Comments

g2 Ecopuck plus VR2C
s1 hotspot with MF DAT
s2 gpctd plus D0
s3 pco2 plus ph

Technician Signature:

Note: Once vehicle is launched the following tasks must be completed

1. Clear alarms
2. Log vehicle modifications in notebook

- 3. Vehicle on mission
- 4. Create *LAUNCHED* comment into WGMS
- 5. Upload photos to gallery website with album name: *YYYY-MM-DD VehicleName*

Save & Submit

Print