

Inline Cable Colour Code 1 Black 2 White 3 Red 4 Green 5 Orange 6 Blue 7 White/Black 8 Red/Black (Bulkhead Leads Number Tagged)		Connector Specifications Single Contact Rating : 300 V @ 5 Amp Connector Rating 2 pins : 300 V @ 5 Amp Connector Rating 3-4 pins : 300 V @ 4 Amp Connector Rating 5-8 pins : 300 V @ 3 Amp Insulation Resistance : >200 megaohm Contact Resistance : <0,01 ohm Wet Matings : >500 Temp. Rating : -4° to +60° C 25° to 140° F Depth Rating : 700 bar - 10.000 psi	
		Material Specifications Connector Body : Neoprene (CR) Bulkhead Body : Brass UNS-C36000 Pin mat : Gold Plated Beryllium Copper UNS-C17300 Socket mat : Gold Plated UNS-C36000 F.H. Nuts & Washers : Brass UNS-C36000 'O' Rings : Nitrile Locking Sleeve : Delrin Snap Ring : AISI 302 Inline Cable (60 cm) : 20 AWG 0,5 mm ² Rubber BH Leads (30 cm) : 22 AWG 0,32 mm ² Teflon Options : See index pages	
		Dimensions in mm. Threads in inches. 1 inch = 25,4 mm. 1 mm = 0,03937 inch. Modification rights reserved Drawing No. SE 300-62	