

FALMAT BLUE PU Jacket
P.N. FM041304SA2

1	Dark Blue	22 AWG	RS232 TX/485	1
2	GRN	22 AWG	RS232 RX/485	2
3	Light Blue	20 AWG + RG179 Shield	Power and video gnd	3
4	WHT	22 AWG	Spare	4
5	ORG	20 AWG	+24 VDC	5
6	RED	22 AWG	+12 VDC	6
7	YEL	22 AWG	Spare - Video Sync	7
8		RG179 core	Video Core	8
9	GRY	22 AWG	Spare	9
10		cable foil shd -drain wire	Cable Shd - Earth Gnd	10

MINK10 CCP

MINK10 CCP

← 20 ft →

Note: Pin 3 should be terminated to both the light blue 20 AWG wire and the RG179 video shield.

		Monterey Bay Aquarium Research Institute 7700 Sandhold Road, Moss Landing, CA 95039			
		Title DPIV: Aux Camera Cables		Project <Project>	
Engineer <Engineer>	Size A	Document Number <Doc>	Part Number <Part Number>	Project File <Project File>	Rev <Rev>
Designer <Designer>	Date: Wednesday, August 09, 2017		Sheet 1 of 1		