

Datasheet

iHPT 5000 Inverted Ultra-Short BaseLine and Telemetry Transceiver



Description

The iHPT 5000 Inverted Ultra-Short BaseLine (iUSBL) and Telemetry Transceiver is a new high performance platform which supports Sonardyne Wideband®2 6G® instruments and offers significant improvements in acoustic positioning and telemetry performance.

The advanced multi-element processing enables transponders to be positioned more precisely, more quickly and more robustly due to improvements in signal processing algorithms and array design. When used as part of a complete USBL system such as Marksman or Ranger 2 and tightly integrated with Sonardyne's Lodestar attitude, heading and inertial navigation sensor, class leading performance in all water depths is achieved.

New functionality, such as 'Discovery Mode' which enables user to automatically detect previously deployed transponders including their configured address and

channel, makes the system easier to use. The iHPT 5000 also fully supports 6G LBL operations via Fusion LBL software.

The HPT transceiver is also a highly capable acoustic telemetry transceiver. Its multiple simultaneous channels enable robust high speed telemetry reception from Sonardyne's 6G subsea transponder modems and data loggers so reducing valuable vessel time.

Manufactured in titanium, the iHPT 5000 is intended to be fitted to deep water subsea equipment such as a towfish.

The array has been adapted for deep water operation from the tried and tested geometry of the HPT 5000.

Key features

- High performance USBL transceiver utilising Wideband®2 ranging and telemetry offer improved USBL precision and robustness

- Enhanced USBL array designs for improved noisy vessel and deepwater performance
- True simultaneous tracking of multiple transponders providing high update rates
- Seamless simultaneous positioning and telemetry of data whilst tracking
- Sonardyne Wideband 1, 2 and HRP400 ranging mode compatible
- Built in health checks including array and electronics diagnostics
- Discovery mode allows users to automatically scan for transponders deployed within acoustic range
- In water ambient noise monitoring
- Integral robust High Data Rate telemetry for fast acquisition of data from subsea instruments – reduces costly vessel time
- Compatible with Marksman LUSBL, Ranger 2 USBL and Fusion 6G LBL systems

Specifications

iHPT 5000 Inverted Ultra-Short BaseLine and Telemetry Transceiver



Feature		Type 8191-000-01
Operational Frequency		MF (19-34 kHz)
Transceiver Performance	Operating Range	Up to 7,000 m
	Acoustic Cover	Up to $\pm 90^\circ$
	Range precision	Better Than 15 mm
	Positioning Repeatability	All Transceivers Tested to Better Than 0.1% of Slant Range 1 Drms
Transmit Source Level	SL = dB re 1 μ Pa @ 1 m	200 dB
	Tone Equivalent Energy (TEE)*	206 dB (13 J _A)
Electrical		24 or 48 V DC ($\pm 10\%$), Typical 15 W, Max 120 W
Communication		RS485 or RS232, Baud Rate Switchable. Optional Ethernet, 100Base-T
Mechanical Construction		Titanium
Depth Rating		7,000 m
Dimensions; Length x Diameter		365 mm x 240 mm
Weight**		37 kg

Note: The absolute accuracy of the system is dependent upon the quality of external attitude and heading sensors, beacon source level, vessel noise, water depth, mechanical rigidity of the transceiver deployment machine, SV knowledge and proper calibration of the total system using CASIUS.

*TEE – WBv2+ signals are 4x the duration of Sonardyne tone signals (WBv1 & WBv2 are 2x). The TEE figure shows the operational performance when comparing wideband and tone systems.

Detection performance is directly related to the signal energy (Joules (Watt seconds)) and not power. WBv2+ signals are longer in duration (greater energy) than WBv1 and Tone, therefore the detection performance is the same or improved for low transmit source levels.

**Estimated Weight.