



Water-Tight & EMI/RFI Shielded *R110-111 Series*


conFORM Series



Key Features:

- Material - Aluminum die-cast: G Al Si 12 / DIN 1775
- Shallow lid, deep body
- Captive stainless steel lid screws
- Neoprene oil and petrol resistant gasket standard. (-40°C up to +80°C)
- EMI/RFI gasket is NOT required as lid to box connection is INSIDE the gasket seal. A patented system with special designed "teeth" in the enclosure bottom provide a lasting and corrosion secure shield.
- Degree of protection NEMA 4X, IP66, DIN 40050
- Temperature Range (-40°C up to +80°C)
- Separate channel system (outside the seal)
- Special developed external mounting feet made from zinc-die-cast. Can be turned through 90°. The fastening holes have engagement lugs for this purpose. (See accessories)
- All sizes have inner blind holes. A mounting plate made of zinc-plated steel is available
- Textured polyester powder coat, light beige/grey RAL 7032. (can be supplied unpainted on special order)
- CSA certified, Type 4, for use with industrial control equipment






1. EMI/RFI enclosure body connection --to lid (see #2 above) is made INSIDE the gasket seal (see #3). This eliminates expensive conducting gaskets and the corrosion problems that can appear later.
2. Lid EMI/RFI edge (link here to lid close up) extends into enclosure and contacts "teeth" (see #1 above) in enclosure body for a positive contact.
3. Gasket (thermoplastic, forprene, silicon free material) outside of EMI/RFI contact points and inside of lid & mounting holes. No need for expensive conducting gasket (see #1 above).
4. Screws and mounting holes outside of gasket seal.
5. Internal mounting shelves placed along both sides of enclosure include blind holes and grounding screws. There are many mounting holes for self tapping screws in both the enclosure & the lid. Can also be used for mounting P.C. boards or plates.
6. Enclosure holes threaded for easy installation and repetitive assembly & disassembly.



Patented "Conform" Series EMI/RFI Shielding Solution

The patented EV joint provides "metal-to-metal" contact for perfect EM shielding and is protected by the seal from dirt and corrosion. "Teeth" on enclosure bottom, further insure a positive connection. This New EV method eliminates the need for a special conductive gasket or screen (required in the common method).

New EV-Enclosure method.



Common Enclosure method.



Accessories (see table below)



External Mounting Feet (for some sizes).

Part No.	Width	Length	Depth (Including Lid)	Mounting Feet
R111-081-000	84	79	44	R501-000-010
R110-081-000	84	79	67	R501-000-010
R111-082-000	84	129	44	R501-000-010
R110-082-000	84	129	67	R501-000-010
R111-083-000	84	179	44	R501-000-010
R110-083-000	84	179	67	R501-000-010
R111-121-000	126	128	60	R501-000-011
R110-121-000	126	128	90	R501-000-011
R111-123-000	126	226	60	R501-000-011
R110-123-000	126	226	90	R501-000-011
R111-161-000	166	166	60	R501-000-012
R110-161-000	166	166	100	R501-000-012
R111-162-000	166	266	66	R501-000-012
R110-162-000	166	266	100	R501-000-012

