


Subconn PUR Cable

Type D-P4TP24#SW



Document no.	2013026SC
Revision	B
Date	11.10.2016
Prepared by	LMR
Approved by	KL

Construction Characteristics

Twisted pairs	0,25 mm² (#24AWG) stranded tinned copper wires 19/.005, twisted together, insulated with Polypropylene, approx. 0,35 mm wall thickness (4 off)
Filler	Rod filler for roundness
Binder	An overall clear tape wrap
Outer jacket	Polyurethane jacket. 85A Shore Hardness. Color black. Nominal thickness approx. 1,27 mm
Color Code	Twisted pair #1: Brown & White/Brown Twisted pair #2: Blue & White/Blue Twisted pair #3: Orange & White/Orange Twisted pair #4: Green & White/Green

Mechanical Characteristics

Diameter	Nom. 9,65 mm
Weight in air	82 kg/km
Weight in seawater	6 kg/km
Minimum bending radius	102 mm
Depth rating	300 m

Electrical Characteristics

Operating voltage	300 V
-------------------	-------