



Monterey Bay Aquarium Research Institute
 (MBARI-Ventana)
 7700 Sandholt Road
 Moss Landing, CA 95039
 USA
 ERIC MARTIN, 831-775-1862

MacArtney Inc.
 2901 W Sam Houston Pkwy N
 Suite D-260
 Houston, TX 77043

Phone No. 0017132667575
 Fax 0017132667519
 Website www.macartney.com
 E-Mail mac-us@macartney.com

Revision 1

Quotation US137789

Delivery Time	9-10 WEEKS ARO
Payment Terms	30 days net
Delivery Mode	Ex works Origin
Validity	30 DAYS
End User	

Date	17 February 2017
Our Reference	Beto Campos Melanie Sisavath
Your Ref.	EMAIL 021717
Customer No.	1331

No.	Description	Quantity	Price	Discount	USD
<u>With reference to your inquiry, we are pleased to quote:</u>					
91101690	Special cables - other 3-SM FIBER SS TUBE, 2C-14AWG, 1-TP 22AWG, WB KEVLAR, PU Custom Tether Cable consists of : 3ea. Single Mode Fiber inside of SS Tube 2ea. 14awg Single conductors, 1,000 volts, 90C rated (Optional color coded) 1ea. Twisted Pair 22awg conductor, 300 volts rated (Optional color coded) All components cabled together with Water Block in all interstices An overall Clear myla tape as a binder Kevlar strength member to provide 7,000 lbs of breaking strength. 0.075" wall Polyurethane Jacket. (color to be advised) Finished diameter 0.440" nominal. Depth rating: <= 400 meters Lengths: 1 x 1,312 ft (400 meters) +/-10%. Unless, otherwise specified. Shipping tolerance: +/-10%	1,312	5.13		6,730.56
Total USD					6,730.56



Page	2
Revision	1

QUOTATION:

The quotation is subject to prior sales.

We hope you will find our proposal satisfactory
and look forward to your response.

Best Regards

MacArtney Inc.

*Declaration/Certificate of Conformance- We declare that standard items shipped were manufactured per specifications in our catalog and certify custom items were manufactured per supplied drawings and specifications. WARRANTY: 12 months from delivery ex works against faulty design and/or manufacture. The warranty includes labor and parts for all work carried out in the manufacturer's work shop. All freight costs to be covered by the buyer. Warranty work carried out outside the manufacturer workshop includes labor and parts. Travel time, travel costs and accommodation to be covered by the buyer. SUBCONN CONNECTORS must always be greased with Molykote M44 per Subconn Handling Instructions. Refer to www.macartney.com/support for more information. Standard items may be returned unused within 90 days. A 20% restock fee may apply. Custom items cannot be cancelled once confirmed confirmed and are not returnable. OTHER TERMS/CONDITIONS: According to NL01E (available on request).