

Shore
Pumphouse

South Bay
PN# SB-51126
450 Meters

Micro Node

J1
Molded or gland fitting

BLUE	SM FIBER		BLUE	SM FIBER	SPARE1
GREEN	SM FIBER		GREEN	SM FIBER	SPARE2
SLATE	SM FIBER		SLATE	SM FIBER	SPARE3
BLACK	SM FIBER		BLACK	SM FIBER	SPARE4
RED	SM FIBER		RED	SM FIBER	nsFOCE
ORANGE	SM FIBER		ORANGE	SM FIBER	nsFOCE
WHITE	SM FIBER		WHITE	SM FIBER	KFA
BROWN	SM FIBER		BROWN	SM FIBER	KFA
RED	14AWG	+375V	RED	14AWG	+375V
ORANGE	14AWG	+375V	ORANGE	14AWG	+375V
BLUE	14AWG	+375V RET	BLUE	14AWG	+375V RET
VIOLET	14AWG	+375V RET	VIOLET	14AWG	+375V RET
GREEN	14AWG	SEAWATER REF	GREEN	14AWG	SEAWATER REF
YELLOW	14AWG	+300V	YELLOW	14AWG	+300V
BROWN	14AWG	+300V RET	BROWN	14AWG	+300V RET



Monterey Bay Aquarium Research Institute
7700 Sandholdt Road, Moss Landing, CA 95039

Title
W01 - nsFOCE Main Tether

Engineer Kecy	Size B	Document Number <Doc>	Layout File <Layout File>	Rev <Rev>
Layout <Layout>		Date: Tuesday, November 26, 2019	Sheet 1 of 1	