

---

**Fwd: RFQ - USA - IB811 - 20180413**

---

**From :** Qi Chen <qc@ibase-usa.com>  
**Subject :** Fwd: RFQ - USA - IB811 - 20180413  
**To :** emartin@mbari.org

Thu, Apr 19, 2018 11:07 PM



Please refer to the following table.

| IB811                              | On board connector type                                                  | Mating connector type        |
|------------------------------------|--------------------------------------------------------------------------|------------------------------|
| CN1 (eDP)                          | I-PEX 20374-030E-31                                                      | I-PEX 20380-030T             |
| CN2                                | A seven-pin Standard SATA data connector.<br>WIN WIN, WATM-07DBN4B2B8UW4 |                              |
| J2, J7 (Backlight / MCU)           | JST B4B-PH-K-S                                                           | JST PHR-4.                   |
| J6 (USB2.0)                        | Hirose DF11-8DP-2DSA                                                     | Hirose DF11-8DS-2C           |
| J1, J3 (LVDS1 / LVDS2)             | Hirose DF20G-20DP-1V                                                     | Hirose DF20A-20DS-1C         |
| J4 (Audio)                         | Hirose DF11-12DP-2DSA                                                    | Hirose DF11-12DS-2C          |
| BAT1 (Backup Battery)              | Molex 53047-0210                                                         | Molex 51021-0200             |
| J10 (SATA Power)                   | JST B4B-XH-A                                                             | JST XHP-4                    |
| J13 (Front Panel)                  | Dupont 2.54mm-pitch pin header (Male)                                    | Dupont 2.54mm-pitch (Female) |
| J16, J17, J12 (COM2 / COM3 / COM4) | Hirose DF11-10DP-2DSA                                                    | Hirose DF11-10DS-2C          |
| J18 (Digital I/O)                  | Dupont 2.00mm-pitch pin header (Male)                                    | Dupont 2.00mm-pitch (Female) |
| J19 (DC_IN Power)                  | JST B2P-VH                                                               | JST VHR-2N                   |

Dr QI Chen

iBASE-USA

510 449 8880

---