

THIS DOCUMENT IS ISSUED IN STRICT CONFIDENCE
ON CONDITION THAT IT IS NOT COPIED REPRINTED
OR DISCLOSED TO A THIRD PARTY EITHER WHOLLY
OR IN PART WITHOUT THE PRIOR WRITTEN CONSENT
OF SOUTH BAY CABLE CORPORATION.


REVISION		
	DESCRIPTION	DATE
A	PVC/Nylon Insulation changed to HDPE. PVC/Mylar tape changed to heat sealable mylar.	7/17/15

SINGLE CONDUCTORS-6 UNITS

Awg No. 22(19x.0063")B/C
DC Resistance @ 20° C ≤ 16.5 Ohms/1000 Ft
HD Polyethylene
Color code: Brown
Red
Orange
Yellow
Green
Blue

INTERSTICES WATERBLOCKED

TAPE
Heat sealable Mylar tape



ESTIMATED VALUES

Nominal O.D. ----- 0.470"
Weight in Air ----- 214 Lb/1000 Ft
Weight in Seawater ----- 137 Lb/1000 Ft
Breaking Strength ----- 8,000 Pounds
Maximum Load ----- 2,000 Pounds
Min. Bend Diameter ----- 14 Inches



Drawn	O.L.	2/18/00	Approval	
Checked			Approval	

E-M CABLE	SB-43285 A
-----------	------------