

THIS DOCUMENT IS ISSUED IN STRICT CONFIDENCE
ON CONDITION THAT IT IS NOT COPIED REPRINTED
OR DISCLOSED TO A THIRD PARTY EITHER WHOLLY
OR IN PART WITHOUT THE PRIOR WRITTEN CONSENT
OF SOUTH BAY CABLE CORPORATION.

REVISION

	DESCRIPTION	DATE	APPROVAL

FILLERS

Plastic Rods

TWISTED PAIRS-2 UNITS

Awg. No.22 (7x 0.010") B/C

DC Resistance @ 20° C ≤ 17.8 Ohms/1,000 Ft.

Polypropylene Insulation

Voltage Rating: 600 V

Two Conductors Twisted

Color Code:

White-Brown


White-Red

Polyurethane Belt (natural color)

INTERSTICES WATERBLOCKED

TAPE

Heat sealable Mylar Tape



STRENGTH MEMBER

5/16" (3 x 19) wire Rope

Polyurethane Jacket

Color: Black

INNER JACKET

Polyurethane

Color: Black

REINFORCEMENT BRAID

GIPS Braid

OUTER JACKET


Polyurethane

Color: Black

ESTIMATED VALUES

Nominal O.D.-----	0.940"
Weight in Air-----	460 Lb/1,000 Feet
Weight in Seawater-----	150 Lb/1,000 Feet
Breaking Strength-----	8,000 Pounds
Min. Bend Diameter-----	20 Inches

**South Bay
Cable**



Drawn	O.L.	4/7/22	Approval		
Checked			Approval		
E-M Cable			SB-51562		