

THIS DOCUMENT IS ISSUED IN STRICT CONFIDENCE  
ON CONDITION THAT IT IS NOT COPIED REPRINTED  
OR DISCLOSED TO A THIRD PARTY EITHER WHOLLY  
OR IN PART WITHOUT THE PRIOR WRITTEN CONSENT  
OF SOUTH BAY CABLE CORPORATION.

REVISION

| REVISION |                                                                                         |         |
|----------|-----------------------------------------------------------------------------------------|---------|
|          | DESCRIPTION                                                                             | DATE    |
| A        | PVC/Nylon Insulation changed to HDPE.<br>PVC/Mylar tape changed to heat sealable mylar. | 7/17/15 |

SINGLE CONDUCTORS-6 UNITS

Awg No. 22(19x.0063")B/C  
DC Resistance @ 20° C ≤ 16.5 Ohms/1000 Ft  
HD Polyethylene  
Color code: Brown  
Red  
Orange  
Yellow  
Green  
Blue

FILLER

Plastic rod

INNER JACKET

Polyurethane  
Color: Black

ARMOR-STEEL WIRES

Two layers GIPS


OUTER JACKET

HD Polyethylene  
Color: Black

INTERSTICES WATERBLOCKED

TAPE

Heat sealable Mylar tape



ESTIMATED VALUES

Nominal O.D. ----- 0.470"  
Weight in Air ----- 214 Lb/1000 Ft  
Weight in Seawater ----- 137 Lb/1000 Ft  
Breaking Strength ----- 8,000 Pounds  
Maximum Load ----- 2,000 Pounds  
Min. Bend Diameter ----- 14 Inches



|         |      |         |          |  |
|---------|------|---------|----------|--|
| Drawn   | O.L. | 2/18/00 | Approval |  |
| Checked |      |         | Approval |  |

E-M CABLE

SB-43285 A