

Systems
Technical
Publication

SERVOSTAR®Cd

with Kollmorgen GOLDLINE®Xt



KOLLMORGEN



6 AMP

3 AMP

Kollmorgen SERVOSTAR® CD Amplifier

- 115 to 230 Volt Single Phase AC Input Power
- Resolver or Encoder Feedback
- Integrated Power Supply
- Fully Digital Control

The SERVOSTAR CD amplifier is a compact, fully digital amplifier designed to simplify installation and system set-up. Three control algorithms and self-tuning (to the load) functionality allows high performance operation to be achieved quickly and easily.

Since not one control algorithm is best for all machines, SERVOSTAR CD contains Pole Placement, PI, and PDFF control algorithms. SERVOSTAR CD utilizes the PC-based **MOTIONLINK®** for Windows™ which automatically takes you through the key steps of installation and start up.

FEATURES:

Servo Control

- Advanced patented sinewave commutation technology provides smooth, precise low-speed control and high-speed performance
- Accurate torque control due to precision balanced current loops with closed loop sensors
- Velocity loop bandwidths to 400 Hz
- Self-tuning to the load
- S-curve acceleration feature for reducing acceleration “jerk” and machine wear
- Patented torque angle control enhances motor performance
- Fully digital control loops
- Compact and attractive rugged metal package for space-saving, modern appearance - metal package minimizes electrical noise

- Pole Placement, PI, and PDFF control options
- Low Pass or Notch Filters for compliant & resonance machines
- Command modes: Torque (analog or serial); Velocity (analog or serial); Position (analog, serial, stored or pulse)
- Two current ratings: 3 & 6 amp RMS/phase continuous
- 3 to 1 peak/continuous current rating

Analog Command:

- 14 Bit analog conversion
- Simple absolute & incremental thru internal profile generator

Easy Connectivity

- Built in encoder equivalent output can eliminate the need for an additional position feedback device
- RS232 or RS485 Communication
- Unique multi-drop configuration allows a PC or PLC to communicate to multiple SERVOSTAR CD amplifiers via single RS-232 connection
- SERVOSTAR CD's versatile communication capabilities make it easy to integrate machine control data directly from the factory floor to your information system
- Analog $\pm 10V$, pulse/direction, master encoder, serial port, command options

Robust Design

- Protection against miswired connection on 24 Volt I/O
- ESD rugged circuit design and fully metallic enclosure
- Self-protecting intelligent power modules
- Full protection against short circuit, overvoltage, undervoltage, heatsink overtemperature, motor overtemperature, overspeed, overcurrent, and feedback loss
- UL , cUL listed, and CE
- Flash memory

Windows Start-up Environment – MOTIONLINK®

- Advanced motion “wizard” automatically walks you through set-up
- Auto configuration function checks for correct wiring of motor and feedback
- PC “Oscilloscope” for measuring real-time motion performance

Motion Indexing

- Stores up to 4 motion profiles in memory
- Start motion through serial command or digital I/O
- Homing functions

Configurable I/O

- 3 digital inputs, 1 digital output, & 1 analog output can be configured to a variety of functions to customize the SERVOSTAR CD to individual machines

AUTO SET-UP

MOTIONLINK® for Windows takes the fear out of setting up a servo system. Designed for the novice as well as the advanced user, **MOTIONLINK** lets users quickly set-up and fine tune system performance.



The SERVOSTAR CD Auto Set-up consists of six steps to completely configure the SERVOSTAR CD and motor for your machine:

Set SERVOSTAR CD for the Power Source. **MOTIONLINK** will tell you if your SERVOSTAR CD was factory programmed for a line voltage. Push okay, if correct, if not, change to the appropriate voltage.

Set SERVOSTAR CD up for the Motor. If the amplifier has been programmed to operate a specific motor, **MOTIONLINK** will indicate the motor type. Push okay and go to the next step. If not, you can select from a listing of standard Kollmorgen motors or enter in the specific nameplate parameters from the motors you will be using.

Setup Feedback Device. Setup your feedback device (encoder or resolver). You can also select auto-config and have MOTIONLINK perform the configuration for encoder systems.

Select the Operational Mode. Set SERVOSTAR CD to run in position, electronic gearing, velocity, or current mode. Set the command to be serial, analog, or I/O.


Tune SERVOSTAR CD for the Load. Simply select the bandwidth you want the system to operate and press the Auto-tune button .

Store SERVOSTAR CD Settings : The final step is storing the parameters in SERVOSTAR CD and archiving on your hard drive or disk.

Now you're ready to run your machine!

ADDITIONAL FUNCTIONS

MOTIONLINK® also includes other features that allow you to fine tune or monitor the performance of the system.



PC Oscilloscope: For closely evaluating system performance MOTIONLINK includes the functionality of an oscilloscope. You can very easily excite the load then review performance graphically on your computer screen.

Direct Terminal Mode: This mode turns your computer into a "dumb terminal." Variables or parameters can be monitored and changed using the SERVOSTAR CD's command language. This mode is ideal for advanced users who want to get directly in the "heart" of the SERVOSTAR CD.



Selectable Tuning Algorithms: No one control scheme is ideal for all applications. SERVOSTAR CD has three control schemes to choose from: Pole Placement (Standard), PI, and PDF. Although the Pole Placement will meet the needs of most applications, PI and PDF control is also available. So whether your critical need is steady speed control, high accelerations or quick response to load variations, etc., SERVOSTAR CD provides the greatest opportunity to achieve the best machine performance.

Monitor Mode: Allows you to jog the motor to monitor key operation variables. Speed and torque can be viewed in real time in linear gauge format. Up to three variables can be monitored at a time.



MOTIONLINK includes many other features like:

- Setting resolution of encoder "equivalent" output
- Activating position limits
- Displaying amplifier status
- Setting acceleration amps
- Limiting max speed or torque

PROGRAMMABLE FUNCTIONS

Current Control/Motor Configuration

Description	Variables
• Conversion to Linear motor units • Digital current loop control receiving serial • Current loop adaptive gain • System current-limiting capability	MOTORTYPE, MPITCH Torque Mode - OPMODE 2 or 3 <i>T or analog command</i> MLGAINC, MLGAINP, MLGAINZ ILIM, ILIM2, IMAX, ISCALE, ISTOP, MICON, MIPEAK

Velocity Control

Description	Variables
• Serial or analog digital velocity loop control • Stepping and jogging capability • Autotuning • Configurable system speed limits • Advanced control algorithms 1. Proportional-Integral (PI) 2. Pseudo-Derivative w/Feed Forward (PDFF) 3. Standard Pole Placement • First & second-order low pass filtering capability • Notch filtering capability • Bandwidths up to 400Hz • Configurable positive motion direction • Toggling capability between velocity and current (torque) control • I/O controlled velocity	Velocity Mode - OPMODE 0 or 1 <i>STEP, JOG or analog command</i> TUNE VLIM, VOSPD, VSCALE COMPMODE GV, GVI KV, KVI, KVFR BW, MJ, LMJR, TF FILTMODE, LPFHZ1, LPFHZ2, COMPFILT FILTMODE, NOTCHHZ, NOTCHBW ANLPFHZ DIR INx, INxMODE INx, INxMODE, MISPEED

Position Control / Motion Indexing

Description	Variables
• Serial digital position loop control • Incremental & absolute positioning with an “in position” indicator • Simple absolute & incremental indexing with triggering capability through either the serial port or the hardware configurable inputs • Homing capability • PID position loop tuning with feed-forward acceleration gain input to both the velocity & current loops and feed-forward velocity gain input to the velocity loop • Software position limits • Configurable integrator dynamics through travel range • Cumulative, revolution, and error position counters • Position configuration parameters	Position Mode - OPMODE 8 MI, MA, INPOS, PEINPOS, MAPOS, MASPEED, MIDIST, & MISPEED INx, INxMODE MH, HOMESPD, HOMESTATE, HOMETYPE, INx, INxMODE GP, GPD, GPI GPAFR, GPAFR2 GPVFR PLIM, PMAX, PMIN GPISATOUT, GPISATIN PFB, HWPOS, PRD, PE INPOS, PEINPOS, PE, PEMAX, PFB, PFBOff

Gear Mode

Description	Variables
• Electronic gearing featuring Pulse Following or Master Encoder capability with resolution up to 3MHz through C8 connector	Position Mode - OPMODE 4 GEAR, GEARMODE, GEARI, GEARO, PEXT, PEXTOFF, VEXT, XENCRES, XENCDir, INxMODE

PROGRAMMABLE FUNCTIONS

Acceleration/Deceleration Control

Description	Variables
• Electronic braking	STOPMODE, ISTOP
• Accel/Decel linear ramping control in velocity mode	ACC, DEC, PROFMODE
• Controlled decelerating	DECSTOP, DISSPEED, DISTIME
when the drive is left enabled or becomes disabled	STOP, HOLD, CWLIM, LIMIDS
also can be used in conjunction with the electronic braking feature	K, S, ACKFAULT, DIS

Feedback Devices

Description	Variables
Device zeroing mode that rotates the motor to an electrical null point	ZERO, IZERO
<u>Resolvers:</u> - Variety of motor/resolver pole combinations - Resolver-zero offsetting - Inter-LSB interpolation between least significant bits - Automatic resolution configuration based on application speed requirements	MPOLES, MRESPOLES MPHASE ILSBMODE RDRES, VMAX
<u>Encoders:</u> - Maximum frequencies to 3MHz before quad - Up to 10 million counts per motor mechanical cycle - Configures automatically - Index pulse offsetting capability for commutation - Variety of encoder types - encoder with or without index - encoder-hall effects with or without index	MENCRES ENCINIT, ENCINITIST, ENCSTART, IENCSTART MENCOFF MENCNTYPE MHINVA, MHINVB, MHINVC

System Communications

Description	Variables
Three communication interfaces: - Serial port - RS232 single & up to 31 axis MultiDrop addressing through C1/C7 connectors - RS485 single & up to 31 axis MultiDrop addressing through C1 connector - Data transmission baud rates of 9600 or 19200 - Configurable Protocol - Interface through Kollmorgen's MotionLink® or a dumb terminal - Differential Analog Input command through C3 connector +/-10v @ 14 bit resolution - signal filtering - signal deadband and offsetting capability	address setting through DIP switch on top of drive ADDR ADDR DUMP, GET, LIST, MLIST, GETMODE hardware DIP switch ECHO, PROMPT, ACKMODE, GETMODE, MSG
- Encoder equivalent output signal with before quad resolution up to 16,384 line/revolution for a resolver-based system and up to 3MHz for an encoder-based system. This eliminates the need for an additional position feedback device. - resolver-based systems: developed through R/D circuit with configurable resolution - encoder-based systems: actual encoder signal from motor	ANLPPHZ ANIN, ANDB, ANOFF, ANZERO ENCOUT, ENCOUTO MENCRES

PROGRAMMABLE FUNCTIONS

Fault and Safety Detection

Description	Variables
• Watchdog faults • General faults • Configurable UnderVolts protection • Overspeed protection • Fatal and non-fatal error coding with text explanation to the host also included is a run-time counter that records the time the error occurred • Configurable motor thermal protection that accepts various thermostat types • Configurable drive thermal protection through the Foldback feature It set the maximum time limit the drive can provide peak current (2:1 Sx, 3:1 Cx) to the motor. • Configurable end-travel limits: - hardware limit switch detection INxMODE where x is 1, 2, 3 - configurable software position limits • Fault relay output • Active disable feature that allows the user to determine how the system should react at the occurrence of a fault. The system can immediately disable, where the motor will coast to a stop, or it can be programmed to a controlled decelerated stop. • Active enable indicator in the status display decimal	ACKFAULT UVMODE, UVTIME, UVRECOVER VOSPD ERR, FLTHIST, FLTCLR TRUN THERM, THERMODE, THERMTYPE, THERMTIME FOLD, FOLDMODE, FOLDBACK CCWLIM, CWLIM, LIMDIS, INx, PLIM, PMAX, PMIN RELAY, RELAYMODE, DISTIME ACKFAULT DECSTOP, DISSPEED, DISTIME, STOPMODE, ISTOP ACTIVE, DRIVEOK, SWEN, READY, REMOTE, DIPEN

Monitoring and Diagnostic Tools

Description	Variables
• Performance recording • System status checking • Control loop monitoring: 1. current/torque 2. speed 3. position • Analog output (configurable) resolution through C3 connector that can be configured to monitor speed, torque, current, power, velocity error, & position following error (Should be used as a monitoring tool only.) • Digital output (configurable) dual-state digital output through C3 connector that toggles according to various absolute current, speed, & position parameter settings. Also can be used to communicate occurrences of Foldback, Brake mode, Drive enable & Encoder INIT complete • Status Display indicator that communicates operational & fault characteristics • Real-time reading of the 10-position DIP switch • Indicator provided for Configurable Inputs	RECDONE, REcing, RECOFF, RECORD, RECRDY, RECTRIG STAT, STATUS, STATUS2 I, IA, IC, ICMD, IMAX, ICONT, V, VCMD, VE PCMD, PFB, PE, HALLS, HWPOS, INPOS, PRD, PEXT ANOUT O1, O1MODE, O1RST, O1TRIG TESTLED DIP, DIPEN, ADDR INx, INxMODE

Others

Description	Variables
• Many enabling and disabling features • Flash firmware memory for easy field installation	K, S, STOP, REMOTE, EN, DIS

SERVOSTAR CD

AMPLIFIER SPECIFICATIONS

Electrical characteristics

- Closed loop velocity bandwidth up to 400 Hz
- Motor current ripple frequency (16-32 kHz)
- Long term speed regulation (0.01%)
- Position loop update rate 500 μ s (2 kHz)
- Velocity loop update rate 250 μ s (4 kHz)
- Commutation update rate 62.5 μ s (16 kHz)
- Current loop update rate 62.5 μ s (16 kHz)

Fault protection

- Output phase to phase short circuit protection
- Overvoltage
- Undervoltage
- Overtemperature (motor and amplifier)
- Overspeed
- Overcurrent
- Feedback loss
- Foldback
- Supply loss
- Excessive position error

Environmental

- Operation range
 - Ambient 0 to 45°C
 - Storage -20°C to 70°C
- Humidity (non-condensing) 10% to 90%

Velocity Loop Compensation

- Vel: PI, PDFF or Pole Placement selectable algorithms
- Factory preset or field tunable
- **MOTIONLINK®** software provides tuning programming via RS-232 or RS-485 serial interface
- Adjustable filters

Position Loop Compensation

- PID

Operational modes

- Torque control — from analog or serial command
- Velocity control — from analog or serial command
- Pulse following / Up-Down count
- Gearing from quad encoder input
- Position control

Inputs

- Analog command: ± 10 V
 Resolver feedback models: 14 bit resolution provides up to 16,000 to 1 dynamic speed range
 Encoder feedback models: 15 bit resolution provides up to 32,000 to 1 dynamic speed range
- Remote enable: 24V
- Three multi-purpose 24V inputs Configurable to: CW limit switch, CCW limit switch, gear enable, start motion, second current limit, change velocity to torque mode, home switch, search for home, move to home registration capture, active disable, control fault relay, hold position plus using two inputs, up to four stored indexes or speeds can be executed
- Pulse command: up/down, pulse/direction, pulse or quadrature encoder format into RS-485 receivers or opto isolators

Communications

- RS-232 or RS-485 serial interface 9600 or 19.2 kb
- Drive-to-Drive multidrop

Outputs

- Fault: contact closure rated for 1 Amp, 24 Volt
- One multi-purpose 24V output configurable to: speed exceeded, current exceeded, amplifier in foldback, brake enable, motion complete, in position, zero speed detect, encoder INIT complete

Diagnostics

- Seven segment LED display
- Error history log
- Internal variable monitoring
- PC scope

Motor Feedback

- Resolver: sine/cosine 2V peak to peak (SERVOSTAR CD provides 4.25V peak to peak for resolver excitation)
- Encoder: 5V differential quadrature with or without Halls, with or without marker, up to 3 MHz before quadrature (12 MHz after quadrature)

Amplifier Ratings

Model	Output Continuous Current Per Phase (RMS/phase)	Output Peak Current Per Phase (1/2 sec)	Rated Output Continuous Power (kW)	Internal Power Dissipation (Watts)	PWM Switching Frequency (kHz)	AC Input Line Voltage (1 phase)	Rated Input Power (kW)	Regen. Option
Cx03	3	9	1.1	37	16	115-230	1.7	ERH-26
Cx06	6	18	2.2	84	8	115-230	2.8	ERH-26

RESISTIVE REGENERATION SIZING/DIMENSIONS

Resistive Regeneration Sizing

Shunt regeneration is required to dissipate energy that is pumped back into the DC bus during load deceleration. The amount of shunt regeneration required is a function of the sum of simultaneously decelerating loads. The loads need to be defined in terms of system inertia, maximum speed, and deceleration time. In addition, the duty cycle must be known. Application Note A-SU-001-H details a calculation method to determine proper regeneration sizing.


Transformer Sizing (Required only for voltage matching)

The SERVOSTAR CD can be connected to a line. Built-in soft-start circuitry protects power supply components and eliminates nuisance tripping of breakers or fuse blowing due to large in-rush currents. Transformers are only required for voltage matching purposes. In this case, the transformer should have a 115 or 230 VAC secondary depending on the operating voltage. The kVA rating of the transformer should take into account not only the servo output load requirements but also losses in the system and power factor. For single phase operated systems such as these, the transformer KVA ratings should be two times the CD amplifier output power rating.

Model	Transformer KVA rating
Cx03	2.2
Cx06	4.4




Model	Watts	Ohms
ERH-26	200	20



Resistive Regen ERH-26

SERVOSTAR Cx03 / 06 DIMENSIONS




	DIM. "A"
3 AMP	67.4 (2.65)
6 AMP	88.4 (3.48)

Dimensions in mm (inches)

SERVOSTAR CD


CONNECTOR INFORMATION

C1 Serial Communications




C7 Inter SERVOSTAR Communications (See manual for pin information)


C8 Remote Pulse or Encoder Input



AC Power Input (Bus)




C4 Encoder Equivalent Output




Cxxx SERVOSTAR CD


C3 User I/O




C2 - Resolver Feedback (from Motor) used on CRxx Models



C2 - Encoder/Hall Feedback (from Motor) used on CExx Models



SYSTEM ORDERING INFORMATION



Kollmorgen GOLDLINE XT

INTRODUCTION



Kollmorgen GOLDLINE® XT30 & XT150 Series

- 0.44 to 4.8 N-m (0.32 to 3.5 lb-ft) Continuous Torque
- Up to 18.7 N-m (13.8 lb-ft) Peak Torque
- 60mm (2.35 in) and 90mm (3.5 in) Square Frames
- Encoder or Resolver Feedback
- Speeds up to 6000 RPM

Kollmorgen **GOLDLINE XT 15** and **30** series servomotors provide high performance, cost-effective solutions in compact, rugged NEMA 23 and 34 packages.

Kollmorgen's patented magnetic design allows high torque-to-inertia for rapid acceleration, while providing extremely low cogging and torque ripple for smooth operation.

The proprietary stator assembly provides more efficient heat transfer for high torque density (compact size), and at the same time increases thermal time constants to allow longer overloads on machines.

The **GOLDLINE XT** series base models designed for use with the **SERVOSTAR® CD** drive come equipped with an integral, industrial grade optical encoder (2048 Lines Per Revolution), and rugged, CE compliant, rotatable connectors. Optional resolver feedback is also available.

FEATURES:

- Multiple stack lengths
- Short overall motor lengths
- Excellent torque-to-inertia ratio
- Low cogging/torque ripple
- Speeds to 6000 RPM standard
- Increased thermal time constant
- English and Metric standard mounting
- UL recognized, CE compliant
- Optimized windings to match **SERVOSTAR CD**
- Rotatable connectors
- Rugged 2048 LPR encoder feedback
- Built-in thermostat (XT30) or thermistor (XT15)
- IP65 sealing

OPTIONS:

- IP67 sealing
- Integral electrically-released brake (24 or 90 VDC)
- Resolver feedback
- Mating connectors

Performance Curves notes (opposite page):


1. Continuous duty operation is with motor mounted to 8" x 12" x 3/8" aluminum faceplate.
2. All curves shown at 60Hz input. Derate max speed and peak power by 15% for 50 Hz operation.
3. For motor models with shaft seals, derate torque at all speeds by 0.026 lb-ft (0.035 N-m).
4. All curves represent typical performance. Always allow appropriate safety factor when sizing systems.

Kollmorgen GOLDLINE XT and SERVOSTAR CD

XT150 SYSTEM PERFORMANCE CURVES


1 n Motor MT1502A n Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	0.32 0.44
Peak Torque at stall	Tp	lb-ft N-m	0.92 1.25
Max. Speed ¹	Nmax	RPM	6000
Rated Cont. Power ¹	Pr	HP Watts	0.31 231
Rated Speed ¹	Nr	RPM	6000
Motor Inertia ² x 10 ⁻⁴	Jm	lb-ft-s ² kg-m ²	0.076 0.104
Motor Weight	Wt	lb kg	2.4 1.1




2 n Motor MT1504A n Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	0.55 0.74
Peak Torque at stall	Tp	lb-ft N-m	1.50 2.03
Max. Speed ¹	Nmax	RPM	6000
Rated Cont. Power ¹	Pr	HP Watts	0.50 373
Rated Speed ¹	Nr	RPM	6000
Motor Inertia ² x 10 ⁻⁴	Jm	lb-ft-s ² kg-m ²	0.126 0.171
Motor Weight	Wt	lb kg	2.9 1.3




3 n Motor MT1506A n Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	1.00 1.35
Peak Torque at stall	Tp	lb-ft N-m	2.80 3.80
Max. Speed ¹	Nmax	RPM	6000
Rated Cont. Power ¹	Pr	HP Watts	0.90 671
Rated Speed ¹	Nr	RPM	6000
Motor Inertia ² x 10 ⁻⁴	Jm	lb-ft-s ² kg-m ²	0.217 0.294
Motor Weight	Wt	lb kg	4.1 1.9



4 n Motor MT1506B n Amplifier: Cx06

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	1.02 1.38
Peak Torque at stall	Tp	lb-ft N-m	2.88 3.90
Max. Speed ¹	Nmax	RPM	6000
Rated Cont. Power ¹	Pr	HP Watts	0.87 649
Rated Speed ¹	Nr	RPM	6000
Motor Inertia ² x 10 ⁻⁴	Jm	lb-ft-s ² kg-m ²	0.217 0.294
Motor Weight	Wt	lb kg	4.1 1.9



Notes:

1. Values for 230 VAC operation.


2. Values for encoder feedback version. For resolver add: 0.017 x 10⁻⁴ lb-ft-s² (0.023 x 10⁻⁴ kg-m²)

Kollmorgen GOLDLINE XT and SERVOSTAR CD

XT30 SYSTEM PERFORMANCE CURVES


5 Motor MT302A Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	0.95 1.29
Peak Torque at stall	Tp	lb-ft N-m	2.15 2.92
Cont. Power	HP rated W rated	HP Watts	0.79 590
Max. Speed	N	RPM	4500
Motor Inertia $\times 10^{-4}$	Jm	lb-ft-s ² kg-m ²	0.343 0.465
Motor Weight	Wt	lb kg	5.6 2.5




6 Motor MT302B Amplifier: Cx06

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	0.94 1.27
Peak Torque at stall	Tp	lb-ft N-m	2.20 2.98
Cont. Power	HP rated W rated	HP Watts	0.97 720
Max. Speed	N	RPM	6000
Motor Inertia $\times 10^{-4}$	Jm	lb-ft-s ² kg-m ²	0.343 0.465
Motor Weight	Wt	lb kg	5.6 2.5




7 Motor MT304A Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	1.86 2.52
Peak Torque at stall	Tp	lb-ft N-m	4.51 6.12
Cont. Power	HP rated W rated	HP Watts	0.95 710
Max. Speed	N	RPM	3000
Motor Inertia $\times 10^{-4}$	Jm	lb-ft-s ² kg-m ²	0.60 0.81
Motor Weight	Wt	lb kg	7.3 3.3



8 Motor MT304B Amplifier: Cx06

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft N-m	1.81 2.45
Peak Torque at stall	Tp	lb-ft N-m	4.35 5.90
Cont. Power	HP rated W rated	HP Watts	1.76 1310
Max. Speed	N	RPM	6000
Motor Inertia $\times 10^{-4}$	Jm	lb-ft-s ² kg-m ²	0.60 0.81
Motor Weight	Wt	lb kg	7.3 3.3



Notes:


1. Continuous duty operation is based on using 8"x 12"x 3/8" aluminum plate.
2. All curves shown at 60 Hz input, derate max. speed and peak power by 15% for 50 Hz operation.
3. For motor models with shaft seals, derate torque at all speeds by .059 ft-lb (.08 N-m).
4. All curves represent typical performance. Always allow appropriate safety factor when sizing systems.

Kollmorgen GOLDLINE XT and SERVOSTAR CD

XT30 SYSTEM PERFORMANCE CURVES


9 Motor MT306A Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft	2.449
		N-m	3.38
Peak Torque at stall	Tp	lb-ft	6.34
		N-m	8.60
Cont. Power	HP rated	HP	1.10
	W rated	Watts	820
Max. Speed	N	RPM	2500
Motor Inertia x 10 ⁻⁴	Jm	lb-ft-s ²	0.819
		kg-m ²	1.11
Motor Weight	Wt	lb	8.36
		kg	3.8




10 Motor MT306B Amplifier: Cx06

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft	2.45
		N-m	3.32
Peak Torque at stall	Tp	lb-ft	6.09
		N-m	8.26
Cont. Power	HP rated	HP	1.98
	W rated	Watts	1480
Max. Speed	N	RPM	4600
Motor Inertia x 10 ⁻⁴	Jm	lb-ft-s ²	0.819
		kg-m ²	1.11
Motor Weight	Wt	lb	8.36
		kg	3.8




11 Motor MT308A Amplifier: Cx03

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft	3.53
		N-m	4.79
Peak Torque at stall	Tp	lb-ft	8.7
		N-m	11.8
Cont. Power	HP rated	HP	0.90
	W rated	Watts	671
Max. Speed	N	RPM	1500
Motor Inertia x 10 ⁻⁴	Jm	lb-ft-s ²	1.29
		kg-m ²	1.75
Motor Weight	Wt	lb	11.3
		kg	5.1



12 Motor MT308B Amplifier: Cx06

Performance Specification	Symbol	Units	
Cont. Torque at stall	Tc	lb-ft	3.53
		N-m	4.79
Peak Torque at stall	Tp	lb-ft	8.7
		N-m	11.8
Cont. Power	HP rated	HP	1.72
	W rated	Watts	1280
Max. Speed	N	RPM	3000
Motor Inertia x 10 ⁻⁴	Jm	lb-ft-s ²	1.29
		kg-m ²	1.75
Motor Weight	Wt	lb	11.3
		kg	5.1




Notes:

1. Continuous duty operation is based on using 8"x12"x3/8" aluminum plate.
2. All curves shown at 60 Hz input, derate max. speed and peak power by 15% for 50 Hz operation.
3. For motor models with shaft seals, derate torque at all speeds by .059 ft-lb (.08 N-m).
4. All curves represent typical performance. Always allow appropriate safety factor when sizing systems.

Kollmorgen GOLDLINE XT

DIMENSIONS

MT150x




Model	"A" MAX.		"B" REF		"C" REF		"D"		"E"		"F" ±0.5 (±.020)		Key Length	
	w/ brake	w/o brake	w/ brake	w/o brake	w/ brake	w/o brake	NEMA 23	NEMA 65	NEMA 23	NEMA 65	NEMA 23	NEMA 65	NEMA 23	NEMA 65
MT(B)1502	158.70 (6.248)	113.4 (4.465)	140.33 (5.525)	95.31 (3.752)	230.38 (9.07)	185.42 (7.30)	9.513	13.997	38.05	49.99	20.83	30	no	20 (.79)
MT(B)1504	174.24 (6.860)	128.94 (5.077)	155.88 (6.137)	110.85 (4.364)	245.87 (9.68)	200.91 (7.91)	9.525	14.006	38.15	50.01	(.820)	(1.181)	keyway	20 (.79)
MT(B)1506	205.23 (8.080)	160.03 (6.301)	186.97 (7.361)	141.94 (5.588)	277.11 (10.91)	231.90 (9.13)	(.3745)	(.5511)	(1.498)	(1.968)				20 (.79)

Kollmorgen GOLDLINE XT

DIMENSIONS

MT30x



Model	"A" MAX.		"B" MIN.		"D"		"E"		"F" $\pm .76$ ($\pm .030$)		Key Length	
	with brake	without brake	with brake	without brake	NEMA 34	NEMA 100	NEMA 34	NEMA 100	NEMA 34	NEMA 100	NEMA 34	NEMA 100
MT(B)302	165.6 (6.520)	120.1 (4.730)	65.14 (2.565)	19.93 (.785)	9.512-9.525	14.01	73.05	80.03			no	20 (.79)
MT(B)304	183.1 (7.210)	137.7 (5.420)	82.67 (3.255)	37.46 (1.475)	(.3745-.3750)	13.99	73.00	79.99	31.75	30	keyway	20 (.79)
MT(B)306	198.6 (7.820)	153.2 (6.030)	98.16 (3.865)	52.95 (2.085)	12.69-12.70	(.5515)	(2.876)	(3.151)	(1.250)	(1.181)	19 (.75)	20 (.79)
MT(B)308	231.7 (9.120)	186.2 (7.330)	131.2 (5.165)	85.97 (3.385)	(.4995-.5000)	(.5511)	(2.874)	(3.149)			19 (.75)	20 (.79)

Connections:

Motor Receptacle:

Pin	3	- Phase A (brown)
Pin	4	- Phase B (red)
Pin	1	- Phase C (white)
Pin	2	- Ground (green/yellow)
Pin	A	- (Optional)Brake (+) (blue)
Pin	B	- (Optional)Brake (-) (blue)

Encoder Receptacle:

Pin	1	- A (blue)
Pin	2	- $\bar{A}$ (blue/black)
Pin	3	- B (green)
Pin	4	- $\bar{B}$ (green/black)
Pin	5	- Z (violet)
Pin	6	- $\bar{Z}$ (violet/black)
Pin	17	- Hab=S1 (brown)

Pin	16	- Hbc=S2 (gray)
Pin	15	- Hca=S3 (white)
Pin	10	- +5Vdc (red)
Pin	7	- Common (black)
Pin	8	- Thermostat (yellow)
Pin	9	- Thermostat (yellow)


Resolver Receptacle:

Pin	9	- R1 (Red/White)
Pin	5	- R2 (Yel/White)
Pin	7	- S1 (Red)
Pin	3	- S3 (Black)
Pin	8	- S2 (Yellow)
Pin	4	- S4 (Blue)
Pin	2	- Thermostat (Yellow)
Pin	6	- Thermostat (Yellow)

Kollmorgen GOLDLINE XT and SERVOSTAR CD

SYSTEM INTERCONNECT AND SUMMARY

SYSTEM INTERCONNECT DIAGRAM



System Summary and Configurations

Motor	Continuous Torque lb-ft (N-m)	Peak Torque lb-ft (N-m)	Continuous Power HP (W)	Max Speed RPM	Amplifier ¹	Amplifier Cont/Peak Current (RMS/Phase)	Cable Set ^{2,3}	Curve Number
MT1502A	0.32 (0.44)	0.92 (1.25)	0.31 (231)	6000	CE03200-2G1502A1	3/9	CS-SS-CHA1HE-03	1
MT1504A	0.55 (0.74)	1.72 (2.33)	0.50 (373)	6000	CE03200-2G1504A1	3/9	CS-SS-CHA1HE-03	2
MT1506A	1.00 (1.35)	3.41 (4.62)	0.90 (671)	6000	CE03200-2G1506A1	3/9	CS-SS-CHA1HE-03	3
MT1506B	1.02 (1.38)	3.44 (4.66)	0.87 (649)	6000	CE06200-2G1506B1	6/18	CS-SS-CHA1HE-03	4
MT302A	1.00 (1.36)	2.38 (3.23)	0.83 (619)	4500	CE03200-2G302A1	3/9	CS-SS-CHA1HE-03	5
MT302B	0.99 (1.34)	2.38 (3.23)	1.02 (761)	6000	CE06200-2G302B1	6/18	CS-SS-CHA1HE-03	6
MT304A	1.95 (2.64)	5.46 (7.40)	1.00 (746)	3000	CE03200-2G304A1	3/9	CS-SS-CHA1HE-03	7
MT304B	1.90 (2.58)	5.46 (7.40)	1.85 (1380)	6000	CE06200-2G304B1	6/18	CS-SS-CHA1HE-03	8
MT306A	2.61 (3.54)	8.47 (11.5)	1.15 (857)	2500	CE03200-2G306A1	3/9	CS-SS-CHA1HE-03	9
MT306B	2.58 (3.50)	8.50 (11.5)	2.08 (1550)	4600	CE06200-2G306B1	6/18	CS-SS-CHA1HE-03	10
MT308A	3.72 (5.04)	14.1 (19.2)	0.95 (708)	1500	CE03200-2G308A1	3/9	CS-SS-CHA1HE-03	11
MT308B	3.72 (5.04)	14.1 (19.1)	1.81 (1350)	3000	CE06200-2G308B1	6/18	CS-SS-CHA1HE-03	12

Notes:

¹ Part numbers shown are for encoder feedback. For resolver feedback: CRxx200-2Gxxxx1

² Part numbers shown are for encoder feedback. For resolver feedback: CS-SS-CHAAHBE-03

³ Cable part numbers reflect 3 meter length. Cables are available in 3, 6, and 9 meter lengths (-03, -06, -09).

Maximum encoder cable length is 30 meters. Maximum resolver cable length is 75 meters.

Electrically Released Brake

Motor	Input Voltage ¹ VDC	Input Current ADC	Static Holding Torque ² lb-ft (N-m)	Inertia lb-ft-s ² (kg-m ²)	Max Speed RPM
MTB15xxx	90	0.071	1.14(1.55)	.0000074(.00001)	12000
MTC15xxx	24	0.33	1.14(1.55)	.0000074(.00001)	12000
MTB3xxx	90	0.18	4.4(5.97)	.0000125(.0000169)	6000
MTC3xxx	24	0.75	4.4(5.97)	.0000125(.0000169)	6000

Notes:

¹ ± 10% on inputs

² Static holding torque only. Must not be used in dynamic braking.


Kollmorgen GOLDLINE XT and SERVOSTAR CD

ORDERING INFORMATION

External Regen Resistor Module:	ERH-26	200 Watts
Communications Cable:	A-97251-004	RS-232 communications cable
Connector Kit:	CK100	Mating connectors* for C1, C2, C4, C7 & C8 *Screw terminal mating connectors C3 and C5 are included with the SERVOSTAR CD amplifier.

Note: Custom mechanicals - special shafts, keyways, and mounting are available.
Contact the Kollmorgen Customer Support Network (1-800-77 SERVO) for more information.

Ordering Information



Kollmorgen Sales Offices

E-mail: servo@kollmorgen.com

Internet: <http://www.kollmorgen.com>

Motion Technologies Group

1-800-77 SERVO

E-mail: servo@kollmorgen.com

Americas

Radford, VA

Tel: (800) 77 SERVO

Fax: (540) 639-1640

Asia Pacific & Far East

Tianjin, China

Tel: (86) 22 2627 1090

Fax: (86) 22 2627 1093

Europe & Middle East

Dusseldorf, Germany

Tel: (49) 203 9979 0

Fax: (49) 203 9979 155

Kollmorgen Manufacturing Locations

Kollmorgen Artus

Avrillé, France

Ho Chi Minh City, Vietnam

Kollmorgen PMI

Commack, NY

Kollmorgen Electro-Optical

Northampton, MA

Kollmorgen Seidel

Dusseldorf, Germany

Kollmorgen Industrial Drives

Radford, VA

Kollmorgen Servotronics

Tel Aviv, Israel

Kollmorgen Inland Motor

Radford, VA

Kollmorgen Tandon Inc

Bombay, India

Kollmorgen Magnedyne

Vista, CA

Kollmorgen Tianjin Industrial Drives

Tianjin, China

Kollmorgen enjoys a reputation of excellence based on constant endeavors to update products. Information in this brochure is subject to change.

Windows is a registered trademark of Microsoft Corporation.

Kollmorgen SERVOSTAR, MOTIONLINK, Kollmorgen GOLDLINE, Kollmorgen SILVERLINE, PLATINUM, and MOTIONEERING are trademarks of Kollmorgen.

KOLLMORGEN