

Gemini 720is

Real-time multibeam imaging sonar



Applications

- ROV/AUV navigation
- Obstacle avoidance
- Target recognition
- Search and Recovery
- Object detection

The 720is is a key product in Tritech's renowned multibeam sonar range and offers a realtime, high frequency imaging solution. The Gemini 720is operates at 720kHz and this combined with Tritech's state-of-the-art processing electronics, produces images of superb clarity in harsh and deep water applications.

Benefits

- Near field focusing
- 4mm / 0.2in range resolution
- Clear wide angle field of view
- Suitable for low visibility environments
- Easier interpretation of sonar imagery

Features

- 720kHz operating frequency
- CHIRP processing
- Wide 120° field of view
- Real-time updates for video like imagery
- Integrated velocimeter for accurate ranging

With 120° field of view and a fast update rate, the Gemini 720is is ideal for poor visibility environments.

The Gemini 720is is supplied with Genesis, Tritech's data acquisition and logging software, which offers users the ability to network and operate the sonar along with a range of other Tritech sensors from a single software interface.

The Genesis software offers additional features such as target tracking and already allows you to run a number of other Tritech sensors alongside your Gemini 720is such as MicronNav 200 USBL tracking system and Mechanical scanning sonars.

Key Specification	
Operating frequency	720kHz
Angular resolution	1.0° acoustic, 0.25° effective
Range	0.2m - 120m / 0.6in - 394ft
Supply voltage	19V to 74V DC
Power requirement	16W - 27W (range dependent)
Main port protocol	Ethernet or VDSL
Dimensions	271mm x 135mm x 107mm / 10.67in x 5.32in x 4.22in
Depth rating	1000m / 3281ft or 4000m / 13123ft
Weight in air	3.40kg / 7.50lbs or 5.00kg / 11.02lbs
Weight in water	1.30kg / 2.86lbs or 3.00kg / 6.61lbs


Acoustic Specifications		Software	Minimum	Recommended
Operating frequency	720kHz	Included	Genesis	
Angular resolution	1.0° acoustic, 0.25° effective	Processor	2GHz	3GHz Quad Core
Range	0.2m - 120m / 0.6in - 394ft	Graphics	3D hardware accelerated graphics card	
Number of beams	512	SDK	Available on request	
Horizontal beamwidth	120°	Operating System	Microsoft Windows 7, 10	
Vertical beamwidth	20° (tilted down 10°)			
Range resolution	4mm & 8mm / 0.2in & 0.3in ¹			
Update rate	5 - 97Hz (range dependent)			
Mode of operation	CHIRP or CW			

Interface	
Supply voltage	19V to 74V DC
Power requirement	16W - 27W (range dependent) ²
Main port protocol	Ethernet or VDSL
Auxiliary port protocol	RS232, RS485 (half duplex), TTL in, Ethernet
Connector type	SeaCon 55 series, SubConn FCR 15 series or Schilling SeaNet
VDSL cable length	Maximum length for VDSL and power is 300m / 984ft, if power is provided locally the maximum length for VDSL communication is 500m / 1640ft

Physical specification	
Depth rating	1000m / 3281ft or 4000m / 13123ft*
Weight in air	3.40kg / 7.50lbs or 5.00kg / 11.02lbs
Weight in water	1.30kg / 2.86lbs or 3.00kg / 6.61lbs
Temperature rating (operating)	-10°C to 35°C / 14°F to 95°F
Temperature rating (storage)	-20°C to 50°C / 4°F to 122°F
Dimensions	271mm x 135mm x 107mm / 10.67in x 5.32in x 4.22in

Specification subject to change in line with Trittech's policy of continual product development

Not to scale. Measurements in mm.



Trittech International Limited

Peregrine Road, Westhill Business Park
Westhill, Aberdeenshire AB32 6JL

United Kingdom

Email: sales@tritech.co.uk

Tel: +44 (0)1224 744111

Marketed by:

0703-SOM-00001 Issue: 10

