

MIN-K- 10-CCPL

MIN-K- 10-CCPL



Cable type Falmat Inc. Extreme-Net cable FM022208-11
qty 4, 20 gage wires go to each of the large 14 gage pins
Twists on twisted pairs should be maintained to solder cups as best as possible
Jacket: Green PolyUrethane, dia 0.61"
final cable length approximately 15 feet. exact length not important.