

SES and TT DEPLOYMENT to discuss

1. Stream mast, floats and Trigger trap
2. Stop off mooring line on cleat on STBD A-frame
3. Lower weight on 300 m of 1/2" Spectra line on winch drum
4. 3' of 1/2" chain attached to SES w/ galvanized shackle
5. Put stopper line through ring on 1/2" Spectra line attached to bottom of SES
6. Attach distal end of chain to thimble on Spectra line with galvanized shackle.
7. Raise SES on quick release with pull line.
8. Lower weight and slip stopper (endless line operational from winch cleats) loading quick release mechanism.
9. Tension streaming mooring line
10. Extend A-frame beyond transom
11. Release SES

