




3 x Stainless Steel Loose Tube Fiber Optic:
 Gel Filled Tube
 2 Single Mode Fiber Optic
 Tube Jacketed With HDPE, to 1.70mm (0.067")
 Attenuation 0.6 dB/km @ 1310nm, 0.6 dB/km @1550nm

4 x Fillers

Bedding Sheath to 6.86mm [0.270"]:
 Nom. Wall Thickness 0.72mm [0.028"]
 Material: Black HDPE

Strength Member:
 Galvanized Steel Armour Wire
 With Grease
 Torque Limited
 Layer 1: 24±1 Wires Ø 0.94mm [0.037"]
 Layer 2: 30±1 Wires Ø 0.94mm [0.037"]
 Rated Breaking Strength: 60.0kN [13,530lbs]
 Rated Working Load: 20.0kN [4,510lbs]

Reinforced Outer Sheath:
 Nom. Wall Thickness 1.30mm [0.051"]
 Material: Black HDPE

Mechanical And Physical Properties:

Diameter 13.50±0.65mm [0.530±0.025"]

Cable Is Void Filled

Calculated Weight In Air: 415kg/km [280lbs/kft]

Calculated Weight Sea Water: 270kg/km [180lbs/kft]

MBR: 305mm [12"]