


ELECTRICAL: ■ OPTICAL: ■ RF: ■ ELECTRO-OPTICAL: ■ ELECTRO-RF: ■ OPTO-RF: ■

Applicable Pin Configurations

Cable Description

Cable Part No. & Illustration

3O-1F3 3O-2F2 3O-4F2



3O-POM-ST.12 3O-POM-ST.12 3O-POM-ST.12


Optical & Power/Signal/Control

- 4 x SMF in SS tube
- 6 x 0.52 mm² (20 AWG) 600V power/signal/control
- 71 kN (16,000 lbs.) break strength
- 6000 msw (19,800 ft.) rated
- Ø15.5 mm (Ø.610 in.) nominal OD
- 254 mm (10 in.) bend radius



52A-304 EOM Cable


3T-37



37-16

3T-POM-ST.12

3R-36




36-16

3R-POM-ST.12

Power

- 36 x 2.08 mm² (14 AWG) 600V
- SF overall shield
- 6000 msw (19,800 ft.) rated
- Ø27.4 mm (Ø1.080 in.) nominal OD
- 254 mm (10 in.) bend radius



52A-305 Electrical Cable

3T-12F8




12 OF 8-16

3T-POM-ST.19

Optical & Power

- 12 x SMF in SS tube
- 8 x 1.5 mm² (15 AWG) 600V
- SF overall shield
- 6000 msw (19,800 ft.) rated
- Ø14.0 mm (Ø.550 in.) nominal OD
- 150 mm (6 in.) bend radius



52A-306 EO Cable