

Zimbra**magene@mbari.org**

swagelok part

From : Paul Coenen <coenen@mbari.org>

Thu, Jul 26, 2018 12:02 PM

Subject : swagelok part**To :** Gene Massion <magene@mbari.org>**Reply To :** Paul Coenen <coenen@mbari.org>

The Swagelok fitting that screws into the bottom of the oilyne pump is spec'd as an SS-600-1-6ST. That's the part that is in the drawing, and the part that was ordered. This is a straight tube fitting that has a 3/8" tube fitting on one end, and SAE6 9/16-18 threads on the other end. The pump has an 7/16-20 SAE4 port on the bottom, so... yeah, it don't fit.

The fitting should be an SS-600-1-4ST. That's the 3/8" tube to SAE4 7/16-20 fitting.

I'm going to look for a couple of those, but if I can't find them, I'll order a few...

Paul

~~~~~

Paul Coenen  
coenen at mbari dot org  
Monterey Bay Aquarium Research Institute  
7700 Sandholdt Road  
Moss Landing, CA 95039  
831.775.2099

~~~~~

Work to Eat. Eat to Live. Live to Bike. Bike to Work.
