

RD4 NITRILE LAYFLAT DISCHARGE HOSE



The RD4 model is a black nitrile oil resistant discharge lay-flat hose. It is lighter and less bulky than most rubber discharge hoses, and resists abrasion and weathering. Used in many varied applications, with limited oil and chemical use. Resists kinking and stretching while in service.

Can come with aluminum coupling fittings with (M)NPSM threads and aluminum/brass swivels in standard lengths. Commonly provided with cam and groove or threaded coupling fittings and hose nozzles.

Temperature range is -20F to 200F.

QTY	INNER DIA	OAL	FITTINGS	PRES	BEND R	WT	END PULL	COIL LENGTHS
	(in)	(ft)		(psi)	(in)	(lbs/ft)	(lbs)	(ft)
	1 1/2			150	1.8	0.21	1,900	200
	2			150	2.5	0.3	2,800	200
	3			150	3.7	0.46	3,900	200
	4			150	5.6	0.64	5,280	200
	6			150	7.4	1.11	11,000	200
	8			150	9.9	1.5	14,000	200

NOTES:

CUSTOMER _____		
PROJECT _____		
ENGINEER _____		
CONTRACTOR _____	MODEL:	RD4
CERTIFICATION _____	DRAWN BY: PDB 1/1/04	NITRILE LAYFLAT DISCHARGE