

IntelliDOCK 9555

9555ID



Voice



Data



Docking
Station



Bluetooth

*Pictured with privacy handset
[optional]*

KEY FEATURES

INTELLIDOCK CRADLE

- Securely holds 9555 handset
- Robust design and construction
- Charges 9555 handset ready for use
- Integrated antenna connection
- Handset always charged ready for use

INTEGRATED BLUETOOTH®

- Bluetooth® in-built in cradle
- Supports Bluetooth® Voice Accessories
- Convenient hands-free calling

IN-BUILT RINGER

- In-built ringer for enhanced ring indication

VOICE, DATA, SMS, SBD

- Supports all Iridium voice, data, SMS and SBD services
- Access to prepaid, post paid & crew calling
- Bluetooth® & USB data connectivity

PRIVACY HANDSET

- Supports optional Beam privacy handset
- Auto sensing answer/hang-up intelligence

INSTALLATION

- Supports 9 - 32V DC power input
- Flexible installation via universal mount, also suitable for wall mounting
- Optional 110 - 240V AC plug pack available

QUALITY

- Professional industrial design
- 2 years peace of mind, replacement guarantee
- 100% factory tested
- Full certified, Iridium approved, RoHS, CE, IEC60945

The **IntelliDOCK 9555** is the ideal low cost accessory for using the Iridium 9555 handset for various maritime, transport or fixed site applications.

The purpose built cradle simply docks the 9555 handset securely, providing an integrated antenna, data and power connection that makes it possible to keep all antenna cables and power permanently connected to the dock ready for use. The 9555 handset is easily inserted and removed by the press of a button on the top of the dock making it very easy to remove the 9555 for use out of the dock at anytime.

IntelliDOCK 9555 also supports the use of an optional compact Beam Privacy Handset (RST755) that can be located next to the **IntelliDOCK 9555** for added convenience if required.

APPLICATIONS



Boating



Transport



4WD



In-building

TECHNICAL SPECIFICATIONS

IRIDIUM NETWORK		
9555 Handset	1616 - 1625 MHz	
Compressed Data	10 - 12 kbps	
Voice/Data Modulation	2.4 kbps	
POWER SPECIFICATIONS		
Power input voltage	9 - 32 V DC, 2A max	
AC Power Pack	90-250V AC 50-60Hz, Output 12V 45W	
Power Consumption (AMPS)		
Stand-by * - incl handset	45mA	0.5W
Transmit - incl handset	0.5mA	6W
Sleep Mode	18mA	0.2W
*When battery charged		
PHYSICAL SPECIFICATIONS	UNIT ONLY	PACKED
Dimensions - mm	200 x 75 x 65	325 x 140 x 88
Dimensions - inches	7.9 x 3.0 x 2.7	7.2 x 5.1 x 1.0
Weight - kg	0.32	1.3
Weight - lbs	0.7	2.86
ENVIRONMENT SPECIFICATIONS		
Temperature	Degrees C°	Degrees F°
Operating Range	-30 to +70	-22 to +158
Storage	-40 to +85	-40 to 185
Humidity	≤ 93% RH	

CONNECTORS/INTERFACES	
Iridium - Antenna	Fixed Cable to TNC-Female
GPS-Antenna	Fixed Cable to SMA-Female
9-32V DC	4-way microFit (AC/DC adaptor, or DC lead)
Privacy Handset Port	4 pole 3.5mm jack
Data Port	USB Mini Base of Dock
Bluetooth® Voice Only	In-built
BUTTONS/LEDs	
Bluetooth®	Blue/Orange
Mute/Ringer	Red
Backlight	White LED
Handset Release	Top of Cradle, No LED
CERTIFICATIONS	
Iridium Approved	CE Compliance
Electrical Safety	RoHS
EMC Compliance	C Tick
Independent Aeronautical certification MUST be gained prior installation	
KIT CONTENTS	
Beam IntelliDOCK Cradle	
Universal Mounting Bracket (RAM)	
9 - 32V DC Power Cable	
Quick Start Guide	
User Manual	

NETWORK ACCESS FEATURES

- Global coverage - pole to pole
- Low cost airtime rates
- Support all data services
- Support all Voice services

ACCESSORIES

RST710	Beam Mast Antenna
RST714	Beam Whip Antenna
RST715	Magnetic Antenna
RST720	Bolt Mount Antenna
RST725	Bluetooth® Headset including car charger
RST755	Basic Privacy Handset
RST932	Antenna Cable 6m/ 18ft
RST933	Antenna Cable 12m/36ft

APPROVED BEAM RESELLER

www.beamcommunications.com

www.beamcommunications.com



+61 3 8588 4500



+61 3 9560 9055



info@beamcommunications.com