

PO Box 518
620 Applegate St.
Philomath, OR 97370



(541) 929-5650
Fax (541) 929-5277
www.wetlabs.com

Scattering Meter Calibration Sheet

6/27/2013

Wavelength: 700

S/N

FLBB2K-3310

Use the following equation to obtain either digital or analog "scaled" output values:

$$\beta(\theta_c) \text{ m}^{-1} \text{ sr}^{-1} = \text{Scale Factor} \times (\text{Output} - \text{Dark Counts})$$

• Scale Factor for 700 nm	=	1.671E-06 (m ⁻¹ sr ⁻¹)/counts	1.374E-03 (m ⁻¹ sr ⁻¹)/volts
• Output	=	meter output counts	meter output volts
• Dark Counts	=	45 counts	0.0611 volts
Instrument Resolution	=	1.0 counts 0.8824 mV	1.67E-06 (m ⁻¹ sr ⁻¹)

Definitions:

- **Scale Factor:** Calibration scale factor, $\beta(\theta_c)/\text{counts}$. Refer to User's Guide for derivation.
 - **Output:** Measured signal output of the scattering meter.
 - **Dark Counts:** Signal obtained by covering detector with black tape and submersing sensor in water.
- Instrument Resolution: Standard deviation of 1 minute of collected data.