

UBX-G7020

u-blox 7 GPS, GLONASS & QZSS chips

Highlights

- Multi-GNSS engine for GPS, GLONASS, QZSS
- Galileo and Compass ready
- Minimal board space, <30 mm²
- Combines low power consumption and high sensitivity
- Minimal e-BOM, as few as 8 external parts
- Exceptional jamming immunity
- UART, USB, SPI, and DDC(I²C compliant) interfaces



UBX-G7020-CT
3.0 x 3.4 x 0.56 mm



UBX-G7020-KT
5.0 x 5.0 x 0.55 mm



UBX-G7020-KA
5.0 x 5.0 x 0.55 mm

Product description

The UBX-G7020 is the newest family of standalone positioning chips from u-blox. The high performance u-blox 7 multi-GNSS (GPS, GLONASS, QZSS, SBAS – Galileo and Compass ready) position engine delivers exceptional sensitivity and acquisition times.

u-blox 7 features ultra low power consumption, thanks to innovative single die architecture and enhanced software algorithms. This gives the UBX-G7020 best in class power consumption for GLONASS reception.

The extended voltage supply range and 1.8 V and 3.0 V I/O compliance supports a wide variety of user applications. Sophisticated RF-architecture and interference suppression using active continuous wave detection ensure maximum performance even in GPS/GNSS-hostile environments.

The UBX-G7020 is available in your choice of miniature WL-CSP and QFN packages and features an ultra small solution footprint of only 30 mm². The built-in LNA, LDOs and DC/DC converter, and on-chip ROM mean that only the smallest possible external BOM is required. By supporting TCXOs or lower price GNSS oscillators the UBX-G7020 further ensures a minimal Total-Cost-of-Ownership.

The ultra small UBX-G7020-CT is the perfect choice for portable consumer applications with demanding size and cost constraints. With its rigorous Automotive quality and manufacturing standards (AEC-Q100, ISO/TS 16949) the UBX-G7020-KA is ideal for automotive applications.

Product selector

Model	Package	Type	Supply	Interfaces	Features
	Package	GPS QZSS GLONASS Timing Dead Reckoning Precise Point Positioning	1.4 V – 3.6 V 1.75 V – 2.0 V 2.5 V – 3.6 V	UART USB SPI DDC (I ² C compliant)	Programmable (Flash) DC/DC Converter Data logger RTC crystal Oscillator Antenna supply and supervisor Timepulse External interrupt / Wakeup
UBX-G7020-CT	WL-CSP50	• • •	•	• • • •	S • • S C/T S • •
UBX-G7020-KT/KA	QFN40	• • •	•	• • • •	S • • S C/T S • •

C/T = Crystal and TCXO supported

S = supported, may require external components

Features

Receiver type	56-channel u-blox 7 engine GPS & QZSS L1 C/A, GLONASS L1OF, Galileo [*] E1B/C, Compass [*] ready SBAS: WAAS, EGNOS, MSAS		
Navigation update rate	up to 10 Hz		
Accuracy		GPS	GLONASS
	Position	2.5 m CEP	4 m CEP
	SBAS	2.0 m CEP	
Acquisition	Cold starts:	29 s	30 s
	Hot starts:	1 s	3 s
Sensitivity	Tracking:	-162 dBm	-158 dBm
	Cold starts:	-148 dBm	-140 dBm
	Reacquisition:	-160 dBm	-156 dBm
Assistance	AssistNow Online AssistNow Offline AssistNow Autonomous OMA SUPL & 3GPP compliant		
LNA	Built-In		
Oscillator	Crystal or TCXO		
RTC input	32.768 kHz (optional). Real time clock can be derived from GPS crystal or TCXO.		
Antenna Supervision	Short and open circuit detection supported with external circuit		
DC/DC converter	Integrated		
Anti jamming	Active CW detection and removal		
Memory	Optional SQL Flash		
Data logger [*]	Continuous log of position, velocity & time		

^{*} External FLASH required.

Electrical data

Supply voltage	1.4 V to 3.6 V
Digital I/O voltage level	1.65 – 3.6 V
Power Consumption	41 mW @ 1.4V (Continuous) 9 mW @ 1.4V Power Save mode (1 Hz)
Backup Supply	1.4 to 3.6V

Interfaces

Serial interfaces	1 UART
	1 USB
	1 DDC (I ² C compliant)
	1 SPI
Digital I/O	2 configurable time pulses
	2 EXTINT interrupt inputs
	2 GPIO for antenna supervision
Memory	SQL interface

Legal Notice

u-blox reserves all rights to this document and the information contained herein. Products, names, logos and designs described herein may in whole or in part be subject to intellectual property rights. Reproduction, use, modification or disclosure to third parties of this document or any part thereof without the express permission of u-blox is strictly prohibited.

The information contained herein is provided "as is". No warranty of any kind, either express or implied, is made in relation to the accuracy, reliability, fitness for a particular purpose or content of this document. This document may be revised by u-blox at any time. For most recent documents, please visit www.u-blox.com.

Copyright © 2013, u-blox AG

Objective Specification

Packages

UBX-G7020-CT:	50 Pin WL-CSP, 3.4 x 3.0 x 0.56 mm
UBX-G7020-KT/KA:	40 Pin MLF/QFN, 5.0 x 5.0 x 0.55 mm

Environmental data

Operating temp.	-40°C to 85°C
Storage temp.	-40°C to 125°C
Humidity	JEDEC MSL 1
RoHS compliant (lead-free) and green (no halogens)	

Ordering information

UBX-G7020-CT	u-blox 7 GPS/GNSS chip, 50 Pin WL-CSP
UBX-G7020-KT	u-blox 7 GPS/GNSS chip, 40 Pin QFN
UBX-G7020-KA	u-blox 7 GPS/GNSS chip, 40 Pin QFN, automotive grade

Contact us

HQ Switzerland / EMEA +41 44 722 7444 info@u-blox.com	India +91 959 1302 450 info_in@u-blox.com
Americas +1 703 483 3180 info_us@u-blox.com	Japan +81 3 5775 3850 info_jp@u-blox.com
APAC – Singapore +65 6734 3811 info_ap@u-blox.com	Korea +82 2 542 0861 info_kr@u-blox.com
China +86 10 68 133 545 info_cn@u-blox.com	Taiwan +886 2 2657 1090 info_tw@u-blox.com