



Planetary Gearhead GP 62 A Ø62 mm, 8.0–50.0 Nm



M 1:4

Technical Data

Planetary Gearhead	straight teeth
Output shaft	steel
Bearing at output	ball bearing
Radial play, 7 mm from flange	max. 0.08 mm
Axial play	max. 1 mm
Max. axial load (dynamic)	120 N
Max. force for press fits	1000 N
Direction of rotation, drive to output	=
Max. continuous input speed	3000 rpm
Recommended temperature range	-30...+140°C
Number of stages	1 2 3
Max. radial load, 24 mm from flange	240 N 360 N 570 N

- Stock program
- Standard program
- Special program (on request)

Part Numbers

Gearhead Data

		110499	110501	110502	110503	110504	110505	110506	110507	110508
1 Reduction		5.2:1	19:1	27:1	35:1	71:1	100:1	139:1	181:1	236:1
2 Absolute reduction		57/11	3591/187	3249/121	1539/44	226223/3179	204687/2057	185193/1331	87723/484	41553/176
3 Max. motor shaft diameter	mm	8	8	8	8	8	8	8	8	8
4 Number of stages		1	2	2	2	3	3	3	3	3
5 Max. continuous torque	Nm	8	25	25	25	50	50	50	50	50
6 Max. intermittent torque at gear output	Nm	12	37	37	37	75	75	75	75	75
7 Max. efficiency	%	80	75	75	75	70	70	70	70	70
8 Weight	g	950	1250	1250	1250	1540	1540	1540	1540	1540
9 Average backlash no load	°	1.0	1.5	1.5	1.5	2.0	2.0	2.0	2.0	2.0
10 Mass inertia	gcm ²	109	100	105	89	104	105	102	88	89
11 Gearhead length L1	mm	72.5	88.3	88.3	88.3	104.2	104.2	104.2	104.2	104.2



maxon Modular System

+ Motor	Page	+ Sensor	Page	Brake	Page	Overall length [mm] = Motor length + gearhead length + (sensor/brake) + assembly parts						
RE 50, 200 W	133					180.6	196.4	196.4	196.4	212.3	212.3	212.3
RE 50, 200 W	133	HEDS 5540	430			201.3	217.1	217.1	217.1	233.0	233.0	233.0
RE 50, 200 W	133	HEDL 5540	432			201.3	217.1	217.1	217.1	233.0	233.0	233.0
RE 50, 200 W	133	HEDL 9140	437			243.0	258.8	258.8	258.8	274.7	274.7	278.7
RE 50, 200 W	133			AB 44	484	243.0	258.8	258.8	258.8	274.7	274.7	278.7
RE 50, 200 W	133	HEDL 9140	437	AB 44	484	256.0	271.8	271.8	271.8	287.7	287.7	287.7
EC 45, 250 W	215					216.6	232.4	232.4	232.4	248.3	248.3	248.3
EC 45, 250 W	215	HEDL 9140	436			232.2	248.0	248.0	248.0	263.9	263.9	263.9
EC 45, 250 W	215	Res 26	439			216.6	232.4	232.4	232.4	248.3	248.3	248.3
EC 45, 250 W	215			AB 28	481	224.0	239.8	239.8	239.8	255.7	255.7	255.7
EC 45, 250 W	215	HEDL 9140	436	AB 28	481	241.0	256.8	256.8	256.8	272.7	272.7	272.7