



Revision Number: 012.0

Issue date: 10/12/2017

1. PRODUCT AND COMPANY IDENTIFICATION

Product name:	LOCTITE SF 7070 ODC FREE CLEANER known as ODC-Free Cleaner & Degreaser	IDH number:	135310
Product type:	Solvent based cleaner	Item number:	20162
Restriction of Use:	None identified	Region:	Canada
Company address:	Contact information:		
Henkel Canada Corporation	Telephone: +1 (905) 814-6511		
Meadowpine Boulevard 2515	MEDICAL EMERGENCY Phone: Poison Control Center		
Mississauga, Ontario L5N 6C3	1-877-671-4608 (toll free) or 1-303-592-1711		
	TRANSPORT EMERGENCY Phone: CHEMTREC		
	1-800-424-9300 (toll free) or 1-703-527-3887		
	Internet: www.henkelna.com		

2. HAZARDS IDENTIFICATION

EMERGENCY OVERVIEW

DANGER: FLAMMABLE LIQUID AND VAPOR.
MAY BE FATAL IF SWALLOWED AND ENTERS AIRWAYS.
CAUSES SKIN IRRITATION.
MAY CAUSE AN ALLERGIC SKIN REACTION.
CAUSES SERIOUS EYE IRRITATION.

HAZARD CLASS	HAZARD CATEGORY
FLAMMABLE LIQUID	3
SKIN IRRITATION	2
EYE IRRITATION	2A
SKIN SENSITIZATION	1
ASPIRATION HAZARD	1

PICTOGRAM(S)



Precautionary Statements

Prevention: Keep away from heat, sparks, open flames, hot surfaces - no smoking. Keep container tightly closed. No release into water. Use explosion-proof equipment. Use non-sparking tools. Take action to prevent static discharges. Avoid breathing vapors, mist, or spray. Wash affected area thoroughly after handling. Contaminated work clothing should not be allowed out of the workplace. Wear protective gloves, eye protection, and face protection.

Response: IF SWALLOWED: Immediately call a physician or poison control center. If on skin (or hair): Take off immediately all contaminated clothing. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Do NOT induce vomiting. If skin irritation or rash occurs: Get medical attention. If eye irritation persists: Get medical attention. Take off contaminated clothing. In case of fire: Use foam, dry chemical or carbon dioxide to extinguish.

Storage: Store in a well-ventilated place. Keep cool. Store locked up.

Disposal: Dispose of contents and/or container according to Federal, State/Provincial and local

IDH number: 135310

Product name: LOCTITE SF 7070 ODC FREE CLEANER known as ODC-Free Cleaner & Degreaser

governmental regulations.

Classification complies with Canadian Hazardous Products Regulations (WHMIS 2015) and is consistent with the provision of the United Nations Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

See Section 11 for additional toxicological information.

3. COMPOSITION / INFORMATION ON INGREDIENTS

Hazardous Component(s)	CAS Number	Weight %*
Distillates petroleum, hydrotreated light, <0.1% benzene	64742-47-8	80 - 90
D-Limonene	5989-27-5	10 - 20

* Exact percentages may vary or are trade secret. Concentration range is provided to assist users in providing appropriate protections.

4. FIRST AID MEASURES

Inhalation:	Move to fresh air. If breathing is difficult, give oxygen. If not breathing, give artificial respiration. Get medical attention.
Skin contact:	Wash with soap and water. Remove contaminated clothing and footwear. If symptoms develop and persist, get medical attention.
Eye contact:	Immediately flush eyes with plenty of water for at least 15 minutes. If eye irritation persists, consult a specialist.
Ingestion:	DO NOT induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention.
Symptoms:	See Section 11.

5. FIRE FIGHTING MEASURES

Extinguishing media:	Water spray (fog), foam, dry chemical or carbon dioxide.
Special firefighting procedures:	Wear self-contained breathing apparatus and full protective clothing, such as turn-out gear.
Unusual fire or explosion hazards:	Vapors may accumulate in low or confined areas, travel considerable distance to source of ignition, and flash back.
Hazardous combustion products:	Oxides of carbon. Hydrocarbons. Toxic and irritating vapors.

6. ACCIDENTAL RELEASE MEASURES

Use personal protection recommended in Section 8, isolate the hazard area and deny entry to unnecessary and unprotected personnel.

Environmental precautions:	Do not allow product to enter sewer or waterways.
Clean-up methods:	Remove all sources of ignition. Ensure adequate ventilation. Isolate area. Keep unnecessary personnel away. Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder, sawdust). Store in a closed container until ready for disposal. Refer to Section 8 "Exposure Controls / Personal Protection" prior to clean up.

7. HANDLING AND STORAGE

Handling: Keep container closed. Use only with adequate ventilation. Avoid contact with eyes, skin and clothing. Avoid breathing vapors or mists of this product. Wash thoroughly after handling. Vapors will accumulate readily and may ignite explosively. Refer to Section 8.

Storage: Keep in a cool, well ventilated area away from heat, sparks and open flame. Keep container tightly closed until ready for use.

Shelf Life Statement: Not available.

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Employers should complete an assessment of all workplaces to determine the need for, and selection of, proper exposure controls and protective equipment for each task performed.

Hazardous Component(s)	ACGIH TLV	OSHA PEL	AIHA WEEL	OTHER
Distillates petroleum, hydrotreated light, <0.1% benzene	None	100 ppm (400 mg/m3) PEL	None	None
D-Limonene	None	None	30 ppm (165.5 mg/m3) TWA	None

Engineering controls: Local exhaust ventilation is recommended when general ventilation is not sufficient to control airborne contamination below occupational exposure limits. Provide local ventilation for prolonged use in a confined area. In case of insufficient ventilation, wear suitable respiratory equipment.

Respiratory protection: Use NIOSH approved respirator if there is potential to exceed exposure limit(s).

Eye/face protection: Safety goggles or safety glasses with side shields. Full face protection should be used if the potential for splashing or spraying of product exists. Safety showers and eye wash stations should be available.

Skin protection: Use impermeable gloves and protective clothing as necessary to prevent skin contact.

9. PHYSICAL AND CHEMICAL PROPERTIES

Physical state:	Liquid
Color:	Colorless
Odor:	Citrus
Odor threshold:	Not available.
pH:	Not available.
Vapor pressure:	5 mm hg (20 °C (68°F))
Boiling point/range:	> 148 °C (> 298.4 °F)
Melting point/ range:	Not available.
Specific gravity:	0.7718
Vapor density:	Heavier than air
Flash point:	46 °C (114.8 °F)
Flammable/Explosive limits - lower:	0.7 %
Flammable/Explosive limits - upper:	5 %
Autoignition temperature:	Not available.
Flammability:	Not applicable
Evaporation rate:	Not available.
Solubility in water:	Insoluble
Solubility in water:	Insoluble
Partition coefficient (n-octanol/water):	Not available.
VOC content:	100 %; 780 g/l
Viscosity:	Not available.
Decomposition temperature:	Not available.

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions of storage and use.
Hazardous reactions:	Will not occur.
Hazardous decomposition products:	Oxides of carbon. Hydrocarbons. Irritating organic vapours.
Incompatible materials:	Strong oxidizing agents. Acids and bases.
Reactivity:	Not available.
Conditions to avoid:	Heat, flames, sparks and other sources of ignition. Store away from incompatible materials.

11. TOXICOLOGICAL INFORMATION

Relevant routes of exposure: Skin, Inhalation, Eyes, Ingestion

Potential Health Effects/Symptoms

Inhalation:	May cause respiratory tract irritation.
Skin contact:	Causes skin irritation. May cause allergic skin reaction.
Eye contact:	Causes serious eye irritation.
Ingestion:	Principal hazard of ingestion is aspiration into the lungs and subsequent pneumonitis.

Hazardous Component(s)	LD50s and LC50s	Immediate and Delayed Health Effects
Distillates petroleum, hydrotreated light, <0.1% benzene	None	Irritant, Lung
D-Limonene	Oral LD50 (Mouse) = 5,600 - 6,600 mg/kg	Irritant

Hazardous Component(s)	NTP Carcinogen	IARC Carcinogen	OSHA Carcinogen (Specifically Regulated)
Distillates petroleum, hydrotreated light, <0.1% benzene	No	No	No
D-Limonene	No	No	No

12. ECOLOGICAL INFORMATION

Ecological information: Not available.

13. DISPOSAL CONSIDERATIONS

Information provided is for unused product only.

Recommended method of disposal: Follow all local, state, federal and provincial regulations for disposal.

14. TRANSPORT INFORMATION

The transport information provided in this section only applies to the material/formulation itself, and is not specific to any package/configuration.

Canada Transportation of Dangerous Goods - Ground

Proper shipping name:	PETROLEUM DISTILLATES, N.O.S.
Hazard class or division:	3
Identification number:	UN 1268
Packing group:	III

International Air Transportation (ICAO/IATA)

Proper shipping name: Petroleum distillates, n.o.s.
Hazard class or division: 3
Identification number: UN 1268
Packing group: III

Water Transportation (IMO/IMDG)

Proper shipping name: PETROLEUM DISTILLATES, N.O.S.
Hazard class or division: 3
Identification number: UN 1268
Packing group: III

15. REGULATORY INFORMATION**Canada Regulatory Information**

CEPA DSL/NDL Status: All components are listed on or are exempt from listing on the Canadian Domestic Substances List.

United States Regulatory Information

TSCA 8 (b) Inventory Status: All components are listed or are exempt from listing on the Toxic Substances Control Act Inventory.

16. OTHER INFORMATION

This safety data sheet contains changes from the previous version in sections: 2, 11

Prepared by: Product Safety and Regulatory Affairs

Issue date: 10/12/2017

DISCLAIMER: The data contained herein are furnished for information only and are believed to be reliable. However, Henkel Corporation and its affiliates ("Henkel") does not assume responsibility for any results obtained by persons over whose methods Henkel has no control. It is the user's responsibility to determine the suitability of Henkel's products or any production methods mentioned herein for a particular purpose, and to adopt such precautions as may be advisable for the protection of property and persons against any hazards that may be involved in the handling and use of any Henkel's products. In light of the foregoing, Henkel specifically disclaims all warranties, express or implied, including warranties of merchantability and fitness for a particular purpose, arising from sale or use of Henkel's products. Henkel further disclaims any liability for consequential or incidental damages of any kind, including lost profits.