

THIS DOCUMENT IS ISSUED IN STRICT CONFIDENCE  
ON CONDITION THAT IT IS NOT COPIED REPRINTED  
OR DISCLOSED TO A THIRD PARTY EITHER WHOLLY  
OR IN PART WITHOUT THE PRIOR WRITTEN CONSENT  
OF SOUTH BAY CABLE CORPORATION.


| REVISION    |      |          |
|-------------|------|----------|
| DESCRIPTION | DATE | APPROVAL |
|             |      |          |

#### FIBER OPTICS-4 UNITS

4 Single mode (SMF-28) fiber optics  
in a gel-filled stainless steel tube  
Fiber optics are color coded  
Polypropylene jacket  
Color: White

#### SINGLE CONDUCTORS-2 UNITS

Awg No. 18(19x.010")B/C  
DC Resistance @ 20° C ≤ 6.2 Ohms/1000 Ft  
Polypropylene Insulation  
Voltage rating: 600 V  
Color code: Red & Blue



#### STRENGTH MEMBER

Kevlar™

#### JACKET

Polyurethane  
Color: Black

#### ESTIMATED VALUES

|                          |               |
|--------------------------|---------------|
| Nominal O.D. -----       | 0.280"        |
| Weight in Air -----      | 41 Lb/1000 Ft |
| Weight in Seawater ----- | 14 Lb/1000 Ft |
| Breaking Strength -----  | 2,000 Pounds  |
| Maximum Load -----       | 250 Pounds    |
| Min. Bend Diameter ----- | 13 inches     |

South Bay  
Cable



|         |      |         |          |     |         |
|---------|------|---------|----------|-----|---------|
| Drawn   | O.L. | 4/19/01 | Approval | Gas | 4/19/01 |
| Checked |      |         | Approval |     |         |

E-O-M Cable

SB-43701