



PRODUCT NUMBER: 4068-0-00-15-00-00-33-0


4068-0-00-XX-00-00-33-0

Solder mount in .022 mounting hole. Pin material is Phosphor Bronze (PhBr)

Also available on 16mm wide X 8mm pitch carrier tape:

2,000 parts per 13" reel

Order as: 4068-0-57-XX-00-00-33-0



Standard Tolerances:
Lengths: $\pm .005$
Diameters: $\pm .002$
Angles: $\pm 2^\circ$

DESCRIPTION

Nail Head Pin

Current Rating:

Application Specific

Operating Temperature Range:

-55/+125° C (discontinuous)

Mounting Feature:

Through Hole Solder Mount

Tail Type: Soldertail

Mounting Hole: .022" (0,559mm)

Tail Diameter: .018" (0,457mm)

Packaging: 00 - Packaged in Bulk

Shell Plating

10 μ " Gold over Nickel

Contact Plating

ROHS



ADDITIONAL NOTES & SPECIFICATIONS

In the interest of improved design, quality and performance, Mill-Max reserves the right to make changes in its specifications without prior notice. Specifications and tolerances are provided wherever possible. Due to the wide variety of interconnects Mill-Max offers, the specific tolerances vary from product to product. If you need information regarding the tolerance of a particular part, please contact Technical Services.

© 2020 Mill-Max Mfg. Corp.
190 Pine Hollow Rd , Oyster Bay, NY 11771, USA
Phone: 516.922.6000