

		REVISIONS		
ZONE	REV.	DESCRIPTION	DATE	APPROVED

10x 1.5v D-Cell Alkaline

HOT GLUE FISH PAPER ON BOTH SIDES

13.00

2.40

Notes:

- 1) Battery packs need 2' twisted (5 turns per 1") 22AWG teflon coated wires to be used as leaders.
- 2) Assemble fish paper onto battery pack using 3M 3792LM or equivalent hot glue.
- 3) COVER ENTIRE BATTERY PACK WITH HEAT SHRINK INSULATION

Status:

		DIMENSIONS ARE IN INCHES TOLERANCES: FRACTIONAL ± ANGULAR: MACH ± BEND ± TWO PLACE DECIMAL ± THREE PLACE DECIMAL ±	APPROVALS		DATE	Monterey Bay Aquarium Research Institute MBARI 7700 Sandholdt RD. Moss Landing, CA 95039 PH: (831) 775-1700 
			DRAWN	04.26.07		
			CHECKED	JRosal		
			ENGINEER	JRosal		
		MATERIAL	--		PROJECT NO.	15VDC Battery Pack
		FINISH	--		PROJECT	
NEXT ASSY	USED ON		ESP			
APPLICATION		DO NOT SCALE DRAWING	WEIGHT		SIZE	
					A	
					DWG. NO.	REV.
						0
					SCALE:1:2	WEIGHT:
					SHEET 1 OF 1	