



Planetary Gearhead GP 16 A $\varnothing 16$ mm, 0.1 - 0.3 Nm

Metal Version, Sleeve Bearing



Technical Data

Planetary Gearhead	straight teeth
Output shaft	stainless steel, hardened
Bearing at output	sleeve bearing
Radial play, 6 mm from flange	max. 0.06 mm
Axial play	0.02 - 0.10 mm
Max. permissible axial load	8 N
Max. permissible force for press fits	100 N
Sense of rotation, drive to output	=
Recommended input speed	< 8000 rpm
Recommended temperature range	-15 ... +100°C
Extended area as option	-35 ... +100°C
Number of stages	1 2 3 4 5
Max. radial load, 6 mm from flange	8 N 12 N 16 N 20 N 20 N

M 1:1

- Stock program
- Standard program
- Special program (on request)

Order Number

Gearhead Data


	110321	110322	110323	118186	110324	134782	110325	134785
1 Reduction	4.4 : 1	19 : 1	84 : 1	157 : 1	370 : 1	690 : 1	1621 : 1	3027 : 1
2 Reduction absolute	57/13	3249/169	185193/2197	19683/125	10556001/28561	1121931/1625	601692057/371293	63950067/21125
3 Max. motor shaft diameter	2	2	2	1.5	2	2	2	2
Order Number	118184	134777	134778		134780	118187	134783	134786
1 Reduction	5.4 : 1	24 : 1	104 : 1		455 : 1	850 : 1	1996 : 1	3728 : 1
2 Reduction absolute	27/5	1539/65	87723/845		5000211/10985	531441/625	285012027/142805	30292137/8125
3 Max. motor shaft diameter	1.5	2	2		2	1.5	2	2
Order Number		118185	134779		134781		134784	118188
1 Reduction		29 : 1	128 : 1		561 : 1		2458 : 1	4592 : 1
2 Reduction absolute		729/25	41553/325		2368521/4225		135005697/54925	14348907/3125
3 Max. motor shaft diameter		1.5	2		2		2	1.5
4 Number of stages	1	2	3	3	4	4	5	5
5 Max. continuous torque	Nm 0.10	0.15	0.20	0.20	0.25	0.25	0.30	0.30
6 Intermittently permissible torque at gear output	Nm 0.150	0.225	0.300	0.300	0.375	0.375	0.450	0.450
7 Max. efficiency	% 90	81	73	73	65	65	59	59
8 Weight	g 20	23	27	27	31	31	35	35
9 Average backlash no load	° 1.4	1.8	2.0	2.0	2.4	2.4	3.0	3.0
10 Mass inertia	gcm ² 0.08	0.05	0.05	0.05	0.05	0.05	0.05	0.05
11 Gearhead length L1	mm 15.5	19.1	22.7	22.7	26.3	26.3	29.9	29.9



Combination

+ Motor	Page	+ Tacho / Brake	Page	Overall length [mm] = Motor length + gearhead length + (tacho / brake) + assembly parts					
RE 15, 1.6 W	72			37.9	41.5	45.1	48.7	48.7	52.3
RE 16, 3.2 W	73/74			56.0	59.6	63.2	66.8	66.8	70.4
RE 16, 3.2 W	74	MR	243/244	61.0	64.6	68.2	71.8	71.8	75.4
RE 16, 3.2 W	74	MEnc 13	258	62.1	65.7	69.3	72.9	72.9	76.5
RE 16, 4.5 W	75/76			59.0	62.6	66.2	69.8	69.8	73.4
RE 16, 4.5 W	76	MR	243/244	64.0	67.6	71.2	74.8	74.8	78.4
RE 16, 4.5 W	76	MEnc 13	258	65.1	68.7	72.3	75.9	75.9	79.5
A-max 16	101-104			41.0	44.6	48.2	51.8	51.8	55.4
A-max 16	102/104	MR	243/244	46.0	49.6	53.2	56.8	56.8	60.4
A-max 16	102/104	MEnc 13	258	49.1	52.7	56.3	59.9	59.9	63.5
RE-max 17	131-134			41.0	44.6	48.2	51.8	51.8	55.4
RE-max 17	132/134	MR	243/244	46.0	49.6	53.2	56.8	56.8	60.4
EC 16, 15 W	154			55.8	59.4	63.0	66.6	66.6	70.2
EC 16, 15 W	154	MR	245	65.9	69.5	73.1	76.7	76.7	80.3
EC-max 16, 5 W	171			39.6	43.2	46.8	50.4	50.4	54.0
EC-max 16, 5 W	171	MR	245	46.9	50.5	54.1	57.7	57.7	61.3
EC-max 16, 2-wire	172			49.1	52.7	56.3	59.9	59.9	63.5

Option Ball Bearing



Order Number

4.4 : 1	138333	455 : 1	138343
5.4 : 1	138334	561 : 1	138344
19 : 1	138335	690 : 1	138345
24 : 1	138336	850 : 1	138346
29 : 1	138337	1621 : 1	138347
84 : 1	138338	1996 : 1	138348
104 : 1	138339	2458 : 1	138349
128 : 1	138340	3027 : 1	138350
157 : 1	138341	3728 : 1	138351
370 : 1	138342	4592 : 1	138352

Technical Data

Planetary Gearhead	straight teeth
Output shaft	stainless steel, hardened
Bearing at output	preloaded ball bearings
Radial play, 6 mm from flange	max. 0.08 mm
Axial play at axial load	< 4 N 0 mm
	> 4 N max. 0.05 mm
Max. permissible axial load	8 N
Max. permissible force for press fits	25 N
Sense of rotation, drive to output	=
Recommended input speed	< 6000 rpm
Recommended temperature range	-15 ... +100°C
Extended area as option	-35 ... +100°C
Number of stages	1 2 3 4 5
Max. radial load, 6 mm from flange	10 N 15 N 20 N 20 N 20 N
Gearhead values according to sleeve bearing version	