



ADDITIONAL PARTS			
CROSS PIN	316 SS	2	1006852
KEEPER PIN	316 SS	2	1004236
STOP	316 SS	2	1009542
CTD LWR MT. PLATE	DELFIN, 1 X 5 X 8	1	10020166
CTD LWR MOUNT	DELFIN, 1.5 X 2 X 3.5	1	10020167
CTD UPPER MT PLATE	AL 6061, 3/8 X 10 X 10	1	10020165
CTD UPPER MT.,	DELFIN, 2 X 2 X 3.25	1	10020168
CLEVIS WELD BASE,	316 SS, .5 X 5.5 X 9	1	10020169
CLEVIS	316 SS, .75 X 2.5 X 6	1	10020170
PIN RECEIVER	DELFIN, 8 X 2 X 3	1	10020157

BILL OF MATERIALS									
NEXT ASSY Description		NEXT ASSY Number		UNLESS OTHERWISE SPECIFIED TOLERANCES ARE:		APPROVALS DATE		Monterey Bay Aquarium Research Institute MBARI 7700 Sandholdt RD. Moss Landing, CA 95039 PH: (831) 775-1700 	
				1 PLACE DIM ±1/16		DRAWN J SCHOLFIELD 7/23/08			
				2 PLACE DIM ±.02		ENGINEER			
THIRD ANGLE PROJECTION				3 PLACE DIM ±.005		CHECKED			
				ANGLES ±1°		PROJECT NO. 701312			
						PROJECT ESP			
				1. DIMENSIONS ARE IN INCHES 2. DIMENSION LIMITS HELD AFTER PLATING. 3. REMOVE BURRS AND SHARP EDGES .015 MAX. 4. MACHINED FILLET RADII .0150-.030. 5. MACHINED DIAMETERS ON A COMMON CENTERLINE CONCENTRIC WITHIN .005 6. PERPENDICULARITY & PARALLELISM OF MACHINED SURFACES .002 PER INCH. MAX. .012 INCHES FOR SINGLE SURFACE.					
				DO NOT SCALE DRAWING		WEIGHT			
						SIZE B		DWG. NO. 10020148.DWG	
						SCALE 1:24		CAD FILE:	
								SHEET 1 OF 1	

Status: