


Inductive linear sensors

IWRM 30Z8704/S14C

dimension drawing



general data

mounting type	quasi shielded
measuring distance S_d	0 ... 16 mm
resolution	< 0,01 mm (stat.) < 0,01 mm (dynam.)
repeat accuracy	< 0,015 mm
adjustment	external Teach-in
linearity error	$\pm 160 \mu\text{m}$
temperature drift	$\pm 5 \%$ (Full Scale)

electrical data

response time (factory characteristic)	< 2,5 ms
response time (teach in characteristic)	< 3,1 ms
voltage supply range +Vs	15 ... 30 VDC
current consumption max.	20 mA
output circuit	voltage output / PNP
output signal	0 ... 10 VDC
load resistance	> 1000 Ohm
output current	< 10 mA (PNP)
voltage drop V_d	< 5 VDC (PNP)
short circuit protection	yes
reverse polarity protection	yes

mechanical data

type	cylindrical threaded
housing material	brass nickel plated
dimension	30 mm
housing length	62 mm
connection types	connector M12


ambient conditions

operating temperature	-10 ... +70 °C
protection class	IP 67

photo



connection diagram



installation drawing

