


Strainert Co.
12 Union Hill Rd.,West Conshohocken
PA ,19428 ,US
Phone: 610-825-3310
Fax: 610-825-1734
Email: info@strainert.com
Website: http://www.strainert.com

Item # 4-20 ma Internal Amplifier, 4-20 ma Internal Amplifier

4-20 ma Internal Amplifier

Integral signal conditioning, built into the pin, provides a high level 4 – 20 ma output, while maintaining pin ruggedness and durability.
Consult Factory regarding 4-Wire Amplifier



SPECIFICATIONS

Output Signal	4-20 ma Loop Powered
Input	13 to 28 V DC
$R_L \text{ max }^1$	$(V_{\text{supply}} - 13) / .02 \text{ Ohm}$
Non-Repeatability	0.15% FSO (Nominal)
Non-Linearity	0.50% FSO (Nominal)
Hysteresis	0.50% FSO (Nominal)
Operating Temp	15 to 150 °F
Storage Temp	-40 to 160 °F
Electrical Connection	Bendix PT02H-10-6P Brantner MSXJ-4-BCR

¹ 4-20 ma systems