



Suitcase CCU

**CONTROL AND RECORDING
UNIT FOR CAMERA AND LIGHT**

**RUGGED 6.4" COLOR
LCD DISPLAY**

VHS VCR WITH REMOTE

NTSC OR PAL

**VIDEO AND AUDIO
IN/OUT JACKS**

**CLEAR PLASTIC HOOD
FOR WET WEATHER**

**COMPACT – FITS IN A
TRUCK CAB OR BACK SEAT**



The SCCU can be easily transported by one person, set up at the job site within minutes, and includes everything required to operate and monitor DeepSea video cameras and lights while making video and audio recordings. The SCCU continues DeepSea's trend of producing extremely rugged imaging products for real applications at competitive prices. The color LCD display, for example, can withstand mechanical shock that would damage a CRT monitor. The VCR, which is protected during transport within a pop-up rack-mount, "floats" on a leaf spring suspension system. All components are hard-mounted and secure within the Suitcase CCU during transport. An isolation transformer combined with a ground fault circuit interrupt provides 2 layers of electrical safety.

A complete set of input and output connectors maximize the available configurations. For example, the output connections allow for remote monitor/VCR setups for the customer or agency inspectors while the SCCU is positioned with the tender at the scene of diver deployment. Operators can hook up cameras to the SCCU using banana jacks and BNC terminations and lights via the AC outlets, or specify a cable for all components that takes advantage of the 14-pin universal connector. A video titler can be connected in seconds using the auxiliary video connector. Included with the SCCU is a clear plastic rain hood with drawstring that protects the unit during operation in wet environments.

For more information regarding how the SCCU can simplify your diving and imaging operations, contact DeepSea Power & Light or your local DeepSea representative.

Suitcase CCU Specifications

BASE UNIT

Size: 20.75" x 23.25" x 9.00"
(52.7 x 59.0 x 22.9 cm)
Weight: 53 lbs. (24 kg.)
Input Power: (NTSC) 120 VAC, 60 Hz,
(PAL) 240 VAC, 50 Hz
Output Power: 15.0 VDC to camera,
0-140 or 0-240 VAC light
Monitor: 6.4 inch color LCD, NTSC or PAL
Recorder: 11-inch, 2-head, VHS recorder/
player with remote
Video Format: NTSC or PAL
Video Signal: Composite, S-VHS pass-through

INPUT CONNECTORS

Combined camera and light: MS3102A0-27S
Video: One BNC
Audio: One BNC
Optional: SC-4000 and controller

OUTPUT CONNECTORS

Video: One BNC, one S-VHS
Audio: One BNC
Auxiliary Video: One BNC
Camera voltage: Two bananas, +/- DC
Receptacles: One fixed (2 plugs) and one variable (2 plugs) in 120 VAC;
One fixed (1 plug) and one variable (1 plug) in 240 VAC



Specifications subject to change without notice

DEEPSEA POWER & LIGHT • 3855 Ruffin Rd. • San Diego, CA 92123 USA • TEL (858) 576-1261 • FAX (858) 576-0219

Web: <http://www.deepsea.com> • e-mail: info@deepsea.com

Rev. 12/29/99