



ToolBox Camera Control Unit

**BATTERY OR AC
OPERATION**

INTEGRATED MONITOR

FLIP-DOWN SUN SHADE

**DETACHABLE
NEOPRENE SUNBOOT**

**USES STANDARD NICAD
OR NIMH BATTERIES**

**BATTERY CHARGER
AND NICAD INCLUDED**



DeepSea's ToolBox Camera Control Unit – fast and flexible portable monitoring.

The ToolBox CCU is the smallest, most portable topside camera control unit available anywhere. With its small footprint, light weight and battery operation, extension cords and slow setup times are a thing of the past and remote imaging applications are a breeze.

The ToolBox CCU will power any of our cameras and will provide power for both camera and lights on systems with integrated LED lighting, such as the SST-1370.

Front panel features include a power switch, a dimmer knob for the lights (SST-1370), video in/out (RCA jack), auxiliary AC power input and camera connector.

The high-resolution monitor includes an integrated sunshade and a detachable neoprene sunboot for use in direct sunlight. To maximize battery life, an interlock switch automatically shuts off system power when the unit is closed. And best of all, the ToolBox CCU is engineered to use the most commonly available portable power source – Makita® 14.4V NiCAD or NiMH batteries (NiCAD battery and charger included).

ToolBox Camera Control Unit Specifications

BASE UNIT

Length:	39.37 cm (15.50 in.)
Width:	21.72 cm (8.55 in.)
Height:	21.46 cm (8.45 in.)
Weight with battery:	5.44 kg (12 lbs.)
Weight without battery:	4.54 kg (10 lbs.)
Input Power:	14.4VDC/120 VAC
Output Power:	Variable 8.0 to 12.5VDC

MONITOR

5.5 inch B&W EIA standard
700 lines of resolution

INPUT CONNECTORS

SSBH3FS	Camera video in
15VDC in	120VAC wall adaptor

OUTPUT CONNECTORS

Video in/out	EIA standard (RCA jack)
--------------	-------------------------

PIN OUT

- 1 – GROUND
- 2 – POWER
- 3 – VIDEO

CHARGER

Will charge NiCAD or NiMH batteries	
Input	120VAC
Charge Time	1 hour

BATTERY

Voltage	14.4VDC
Current	2.0Ah (NiCAD)
	2.2Ah (NiMH)



Specifications subject to change without notice

DEEPSEA POWER & LIGHT • 3855 Ruffin Rd. • San Diego, CA 92123 USA • TEL (858) 576-1261 • FAX (858) 576-0219

Web: <http://www.deepsea.com> • e-mail: info@deepsea.com

Rev. 12/29/99