



Micro-SeaLite

**1,000 METER
RATING**

**ULTRA-SMALL
DC LIGHT**

**WET/DRY
OPERATION**

**COMPETITIVELY
PRICED**



The Micro-SeaLite is a unique ultra-compact light for applications where size or weight are limiting factors. This low voltage (12 or 24 VDC) light offers high efficiency wide-beam optics. It outperforms 120V tubular "mini" lights that have three times the lamp wattage. The Micro-SeaLite is available in 12W, 20W, and 35W versions with a choice of three beam patterns for each wattage. The unique ground and polished quartz window provides broad, even beams.

Micro-SeaLite Specifications

MECHANICAL

Housing Material: 6061-T6 hard natural anodize with dichromate seal
Diameter: 3.77 cm (1.485 in.)
Length: 6.73 cm (2.65 in.) without connector
Lens: Quartz
Reflectors: Wide flood
Air Weight: 99 g (0.22 lbs.)
Water weight: 50 g (0.11 lbs.)
Mounts: Collar and yoke bracket included

ENVIRONMENTAL

Depth Rating: 1,000 meters (3,250 feet) of seawater

REPLACEMENT LAMPS

The following bi-pin lamps are available:

<u>PART NO</u>	<u>VOLTS</u>	<u>WATTS</u>	<u>COLOR TEMP.</u>	<u>LAMP LIFE</u>
B4-12/12	12	12	3000K	2000 Hrs
B4-12/20	12	20	3000K	2000 Hrs
B4-12/35	12	35	3000K	2000 Hrs
B4-24/20	24	20	3000K	2000 Hrs



Specifications subject to change without notice

DEEPSEA POWER & LIGHT • 3855 Ruffin Rd. • San Diego, CA 92123 USA • TEL (858) 576-1261 • FAX (858) 576-0219

Web: <http://www.deepsea.com> • e-mail: info@deepsea.com

Rev. 12/29/99