



DEEPSEA
POWER & LIGHT

Wet/Dry Multi-SeaLite

**FUNCTIONS IN AIR
OR WATER**

**1,000 METER
DEPTH RATING**

**VARIABLE BEAM
PATTERNS**



The The Wet/Dry Multi-SeaLite is a light designed for applications requiring lights that can function continuously in either water or air. With its unique cooling fins, it can even withstand immersion in water after several hours of burning in air.

Compatibility with DeepSea's other lights is a key benefit to customers. The Wet/Dry Multi-SeaLite uses the same connectors and lamps as DeepSea's popular Multi-SeaLite, eliminating the need for extra cables or spare lamps. It also uses the same yoke mounting brackets. The Wet/Dry Multi-SeaLite uses lamps in 12V, 24V, 120V, or 240V in 50W or 100W. Like nearly all of DeepSea's lighting products, a choice of three beam patterns is available.

With a 1,000 meter depth rating and competitive pricing, the Wet/Dry Multi-SeaLite can be used in a variety of applications. These include above and below waterline hull inspection, tank and pipe inspection (empty or full), any low voltage operation, and more.

Wet/Dry Multi-SeaLite Specifications

MECHANICAL

Housing Material: Anodized aluminum
Length: 16.2 cm (6.4 inches) (with BH3M connector)
Diameter: 10.5 cm (4.125 inches)
Lens: Clear tempered borosilicate
Reflectors: Proprietary design spot, medium flood or wide flood
Air Weight: 909 g (2 lbs.)
Water weight: 227 g (0.5 lbs.)

OPTICAL

Beam patterns (full angle measured to half power point using 120 volt/100 watt lamps):
Wide Flood (WFL): 59 degrees conical
Medium Flood (MFL): 40 degrees conical
Spot (SP): 16 degrees conical

ENVIRONMENTAL

Depth: 1,000 meters (3,280 feet) of seawater

MISCELLANEOUS

Connectors: BH3M type bulkhead connector
XSG-3-BCL type bulkhead connector
Straight molded penetrator

REPLACEMENT LAMPS (Mini-Can screw base)

Low voltage lamps (12V and 24V) are re-based, and are available only from DeepSea Power & Light.

Model Number	Part Number	Volts	Watts	Hours	Color Temp	Lumens
MC-12/50	460-00018	12	50	2000	3000K	950
MC-12/100	460-00026	12	100	1000	3100K	2,200
MC-24/100	460-00099	24	100	2000	3000K	1,800
MC-120/100	460-00053	120	100	1500	2700K	1,600



Specifications subject to change without notice

DEEPPSEA POWER & LIGHT • 3855 Ruffin Rd. • San Diego, CA 92123 USA • TEL (858) 576-1261 • FAX (858) 576-0219

Web: <http://www.deepsea.com> • e-mail: info@deepsea.com

Rev. 12/29/99