

**LARGE ASSORTMENT
OF LAMPS**

**RUGGED, COMPACT
DESIGN**

**MODULAR
REFLECTOR
SYSTEM**

**COMPLETE WITH
BRACKET, LAMP,
CHOICE OF
REFLECTOR**



The SeaLite line of underwater lights is fast becoming the number one choice for every underwater lighting requirement. The original patented standard SeaLite offers exceptional versatility through modular design. Lamp voltages range from 12 VDC to 240 VAC, while wattages range from 50 through 500 watts. All lamps are positive locking bayonet mount, which eliminates the vibration related failures associated with screw base type lamps. Relamping is quickly accomplished without tools by simply unscrewing the front bezel assembly from the light body. The glass-to-metal seal of the envelope to the bezel is never disturbed during the relamping process; this ensures maximum reliability. Modular reflectors provide beam patterns ranging from a medium spot to wide angle—optimal lighting for almost any conceivable application. The SeaLite body and bezel are constructed of hard black anodized aluminum for superior corrosion resistance. The black finish minimizes stray reflections which cause flare in video images. Standard depth rating is 6,000 meters (20,000 feet).

SeaLite Specifications

MECHANICAL

Maximum Outer Diameter:	with VID-1 reflector:	5.7 cm (2.25 in.)
	with VID-2 reflector:	7.4 cm (2.90 in.)
Length:	with NF-1 reflector:	11.7 cm (4.61 in.)
	with VID-1 reflector:	15.0 cm (5.90 in.)
	with VID-2 reflector:	17.0 cm (6.70 in.)
	with NF-1 reflector:	16.2 cm (6.39 in.)
Weight in Air:	with VID-1 reflector:	0.4 kg (13 oz.)
	with VID-2 reflector:	0.6 kg (20 oz.)
	with NF-1 reflector:	0.3 kg (12 oz.)
Material:	6061-T6 aluminum	
Finish:	Hard black anodize	
Lens:	19 and 25 mm handblown pyrex envelope (quartz optional)	
Reflector Options:	Aluminum specular narrow flood (NF-1), Delrin plastic diffuse wide flood (VID-1 low voltage lamps, VID-2 high voltage lamps)	
Beam Pattern:	VID-1 100 degree wide flood VID-2 100 degree wide flood NF-1 60 degree narrow flood	
Depth Rating:	6,000 meter (20,000 foot)	

MISCELLANEOUS

Connector:	LPBH3MP standard, BH3MP, XSG3BCL and others available
Mount:	Multi-position, fully adjustable

MODEL NUMBERS

Low Voltage:	SL-1010 series
High Voltage:	SL-1020 series

REPLACEMENT LAMPS (Dual Contact bayonet base)

Low voltage lamps (12V and 24V) are re-based, and are available only from DeepSea Power & Light

Model Number	Part Number	Volts**	Watts	Hours	Color Temp	Socket Positions		Lumens
						19mm	25mm	
DC-12/50	460-00017	12	50	50	3300K	1	1	1,400
DC-12/100	460-00025	12	100	50	3300K	1	1	3,000
DC-24/150	460-00033	24	150	50	3400K	1	1	5,000
DC-24/250	460-00037	24	250	50	3400K	2	1	8,500
DC-24/300	460-00040	24	300	50	3400K	2	1	10,200
DC-28/150	460-00046	28	150	700	3000K	1	1	2,850
DC-120/100	460-00051	120	100	750	2850K	2	2	1,800
DC-120/150	460-00054	120	150	1000	2900K	2	2	2,800
DC-120/200	460-00056	120	200	50	3200K	2	2	5,500
DC-120/250	460-00058	120	250	2000	3000K	N/A	2	5,000
DC-120/500	460-00062	120	500	2000	2950K	N/A	3	10,450
DC-240/150	460-00078	240	150	1300	2800K	N/A	2	2,300
DC-240/250	460-00100	240	250	2000	2900K	N/A	2	4,200
DC-240/500	460-00083	240	500	2000	2950K	N/A	3	9,500

** 220/230V, 230V, and 240V lamps are used to meet a nominal 240V requirement.



Specifications subject to change without notice

DEEPSEA POWER & LIGHT • 3855 Ruffin Rd. • San Diego, CA 92123 USA • TEL (858) 576-1261 • FAX (858) 576-0219

Web: <http://www.deepsea.com> • e-mail: info@deepsea.com

Rev. 12/29/99