

MINI-CON MASTER PARTS LIST

ITEM	QTY	PART / DESCRIPTION	NOTES		
①	—	INSERT FACE PATTERN		11	
②	1	O-RING	6		13
③	AR	O-RING		6	
④	1	MIN-BCR	1		13
⑤	1	MIN-CIR		2	
⑥	AR	CONTACT PINS	3		11
⑦	1	SPIROLOX		5	
⑧	1	BULKHEAD HEX NUT (OPTIONAL)		5	
⑨	1	BULKHEAD WASHER (OPTIONAL)		5	
⑩	AR	EPOXY (OPTIONAL)		7	
⑪	AR	HOO-K-UP WIRE (OPTIONAL PIGTAILS)		8	
⑫	1	MIN-FCR	1		13
⑬	1	O-RING		6	
⑭	4	SOCKET CAP HEX SCREW (OPTIONAL)		5	
⑮	1	MIN-CCR		1	
⑯	AR	FILL COMPOUND REQUIRED		14	
⑰	1	MIN-CCP/CCR FI BOOT (OPTIONAL)	4		12
⑱	AR	OVERMOLD (OPTIONAL)	4		12
⑲	2	NYLON CABLE TIE (OPTIONAL)		12	
⑳	1	MIN-CCP	1		13
㉑	1	MIN-CIP		2	
㉒	AR	CONTACT SOCKETS	3		11
㉓	1	RETAINING RING		5	
㉔	1	O-RING	6		13
㉕	1	O-RING		6	
㉖	1	SPIROLOX		5	
㉗	1	ENGAGING NUT		10	
㉘	2	ENGAGING NUT WASHER		9	
㉙	1	MIN-DSR		1	
㉚	1	MIN-DSRL (REFER TO ㉙)		1	
㉛	1	MIN-DSP		1	
㉜	1	MIN-DSPPL (REFER TO ㉛)		1	
㉝	1	MIN-PSR		9	
㉞	1	MIN-PSRL (REFER TO ㉝)		9	
㉟	1	MIN-PSP		9	
㊱	1	MIN-PSPL (REFER TO ㉟)		9	
㊲	1	MIN-CCP-PBOF-FWD END		1	
㊳	1	MIN-CCP-PBOF-AFT END		1	
㊴	1	MIN-CCP-PBOF-R/A AFT END		1	
㊵	1	O-RING		6	
㊶	3	8-32 UNC-2A HEX SOCKET SET SCREW/CUP POINT		5	
㊷	1	10-24 UNC-2A SLOTTED PAN HEAD SCREW WITH O-RING		5	
㊸	1	MIN-BCR DUAL O-RING	1		13
㊹	1	O-RING		6	
㊺	1	O-RING	6		13
㊻	1	MIN-CCR-PBOF		1	
NOTES KEY ON REVERSE SIDE					

MINI-CON MASTER PARTS LIST

NOTES:

- 1 MATERIAL: 316 STAINLESS STEEL PER MIL-S-862.
- 2 MATERIAL: GLASS REINFORCED EPOXY, SEA CON® XS-27748
- 3 MATERIAL: COPPER ALLOY & GOLD PLATE PER MIL-G-45204.
- 4 MATERIAL: NEOPRENE MOLDING PER SEA CON® X-5727.
- 5 MATERIAL: HIGH GRADE STAINLESS STEEL.
- 6 MATERIAL: BUNA-N, 70 DUROMETER.
- 7 MATERIAL: EPON 828/CIBA 840.
- 8 MATERIAL: AS SPECIFIED BY CUSTOMER.
- 9 MATERIAL: BLACK DELRIN.
- 10 MATERIAL: COPPER ALLOY 630.
- 11 REF FACE CONFIGURATIONS FOR SIZE OF CONTACTS AND LOCATIONS.
- 12 AN OVERMOLD OR FIELD INSTALLABLE BOOT IS OPTIONAL ON BOTH THE CCP AND THE CCR.
- 13 DOVETAIL GROOVE TO PREVENT LOSS OF O-RING.
- 14 NOT SUPPLIED.