

ARG-FL-75-CGCS-BLK-3672



Alhambra Rubber & Gasket Company Incorporated

9440 Telstar Avenue Suite #9

El Monte, CA. 91731

Phone: 626.401.4160 Fax: 626.401.1660

www.alhambrarubber.com

email: sales@alhambrarubber.com

Compound Description

Fluoroelastomer Rubber Sheet Commercial Grade Cinnamon Scented

ARG Compound

ARG-FL-75-CGCS-BLK-3672

Characteristics

This domestic manufactured commercial grade Fluoroelastomer sheet is designed for applications that are looking for additional chemical resistance and a temperature rating of 350 Deg F. Material is cinnamon scented.

Tensile Strength

1200 PSI per ASTM D412

Elongation %

350 per ASTM D412

Temperature Range

350 Deg F Max operating temp

Durometer / Shore

75A+/-5

Finish

Smooth both Sides

Color

Black

Listed above are typical properties and are provided for your evaluation. These typical properties are not designed to assign set specification requirements. Alhambra Rubber & Gasket Co., Inc. feels that it is up to the end user to determine if a specific material is suitable for a specific application.