

ARG-NBR-60-CG-3675



Alhambra Rubber & Gasket Company Incorporated

9440 Telstar Avenue Suite #9

El Monte, CA. 91731

Phone: 626.401.4160 Fax: 626.401.1660

www.alhambrarubber.com

email: sales@alhambrarubber.com

Compound Description

Nitrile (NBR) Rubber Commercial Grade

ARG Compound

ARG-NBR-60-CG-3675

Characteristics

Excellent resistance to oils, solvents and fuels. Resistant to a broader range of aromatic hydrocarbons than Neoprene. Extreme oil-resistance applications or in contact with fuels and solvents may not be recommended for this product. Inferior resistance to ozone, sunlight, and natural aging, poor resistance to oxygenated solvents.

Tensile Strength

1000 PSI

Elongation %

350

Temperature Range

-16 to +175 Deg F.

Durometer / Shore

60A+/-5

Finish

Smooth Both Sides, Talc Free

Color

Black

Listed above are typical properties and are provided for your evaluation. These typical properties are not designed to assign set specification requirements. Alhambra Rubber & Gasket Co., Inc. feels that it is up to the end user to determine if a specific material is suitable for a specific application.