

Cable Type Falmat FM022208-11-M02
AWG 14 Conductor equivalent is 4 x #20AWG
Waterblocking (Cable Max?) present
Twists on twp should be maintained to solder cups as best as possible.
Jacket:Green Polyurethane
Dia: 0.61"

