



AC TRANSDUCER

RIBXGTV5

Enclosed Self-Powered Split Core Multi-Range (0-20A, 50A, or 100A) AC Transducer with 0-5Vdc Terminal Output



SPECIFICATIONS

Operating Temperature: -30 to 140° F

Humidity Range: 5 to 95% (noncondensing)

Accuracy: 98.3% Full Scale

Loading: RIBXGTV5, (0-20 Amp), 5% Error @ 33 kΩ

RIBXGTV5, (0-50 Amp), 5% Error @ 15 kΩ

RIBXGTV5, (0-100 Amp), 5% Error @ 6.8 kΩ

Max Sense Voltage: 600 Vac

Approvals: UL Listed, UL916, UL864, California State Fire Marshal, C-UL, CE, RoHS

Mounting/Installation: Removable mounting tab provided. The wire clamp locks against the wire being monitored, securing the unit in place.

Sensor Type: Split core with voltage output

DIP SWITCH

1	2	Sensing Range
OFF	OFF	0-20 Amp
OFF	ON	0-50 Amp
ON	OFF	0-100 Amp