



SMT Power Inductors – DO1608 Series



The DO1608 Series has a footprint of only 0.26" × 0.175" (6,6 mm × 4,5 mm). Their high energy storage and very low resistance make them the ideal inductors for DC-DC conversion in notebook computers, PDAs, step-up or step-down converters, flash memory programmers, etc.



For reliable surface mounting, we've designed the DO Series with a flat top and robust temperature deflection to prevent damage during solder reflow.

In addition to the standard versions shown here, custom inductors are available to meet your exact requirements. Coilcraft **Designer's Kit C105** contains three samples each of the standard parts shown as well as all standard values from the DO3316 Series. To order, please contact Coilcraft or visit <http://order.coilcraft.com>.

SPICE models ON OUR WEB SITE OR CD

Part number ¹	L ±20% ² (μH)	DCR max (Ohms)	SRF typ (MHz)	Isat ³ (A)	Irms ⁴ (A)
DO1608C-102	1.0	0.05	130	2.9	2.9
DO1608C-152	1.5	0.05	115	2.6	2.8
DO1608C-222	2.2	0.07	90	2.3	2.4
DO1608C-332	3.3	0.08	70	2.0	2.0
DO1608C-472	4.7	0.09	50	1.5	1.5
DO1608C-682	6.8	0.13	45	1.2	1.4
DO1608C-103	10	0.16	35	1.1	1.1
DO1608C-153	15	0.23	30	0.90	1.2
DO1608C-223	22	0.37	20	0.70	0.8
DO1608C-333	33	0.51	15	0.58	0.6
DO1608C-473	47	0.64	14	0.50	0.5
DO1608C-683	68	0.86	11	0.40	0.4
DO1608C-104	100	1.27	9	0.31	0.3
DO1608C-154	150	2.00	6	0.27	0.25
DO1608C-224	220	3.11	5.5	0.22	0.20
DO1608C-334	330	3.80	5	0.18	0.16
DO1608C-474	470	5.06	4	0.16	0.15
DO1608C-684	680	9.20	3	0.14	0.12
DO1608C-105	1000	13.8	2	0.10	0.07

- Part number on reel label will have a B, C or D suffix to indicate packaging
 - Tested at 100 kHz, 0.1 Vrms, 0 Adc.
 - DC current at which the inductance drops 10% (typ) from its value without current.
 - Average current for 15°C temperature rise from 25°C.
 - Operating temperature range -40°C to +85°C.
 - Electrical specifications at 25°C.
- See Qualification Standards section for environmental and test data.
See Color Coding section for part marking data.



Weight: 128 – 164 mg
Tape and reel: 750/7" reel; 2500/13" reel 12 mm tape width
 For packaging data see Tape and Reel Specifications section.

Coilcraft®

Specifications subject to change without notice. Document 177-1 Revised 04/09/04


1102 Silver Lake Road Cary, Illinois 60013 Phone 847/639-6400 Fax 847/639-1469

E-mail info@coilcraft.com Web <http://www.coilcraft.com>




SMT Power Inductors – DO1608 Series

Typical L vs Frequency



Typical L vs Current



Coilcraft®

Specifications subject to change without notice. Document 177-2 Revised 10/31/03

1102 Silver Lake Road Cary, Illinois 60013 Phone 847/639-6400 Fax 847/639-1469

E-mail info@coilcraft.com Web <http://www.coilcraft.com>